

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bittling Building,
Wichita, Kansas.

RECEIVED
NOV 5 1935
11-5-1935

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

Locate well correctly on above
640 A. Plat

Ellis County. Sec. 13 Twp. 11 Rge. 16 (E) (W)
Lease Name. Bowlby Well # 1.
Lease Owner. The Palmer Oil Corporation
Office Address. Union National Bank Bldg. Wichita, Kansas
Character of Well (Oil, Gas or Dry) Dry Total Depth of Well 3695 Feet
Date, well, completed. October 14th, 1935.
Application for plugging and log of well filed October 14th, 1935.
Application for plugging approved October 14th, 1935.
Plugging Commenced October 14th, 1935.
Plugging Completed October 20th, 1935.
Reason for abandonment of well or producing formation Formation Dry.

If a producing well is abandoned, date of last production 193
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Officer who supervised plugging of this well C. S. McGee.
Producing formation None Depth to top Bottom
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	475'	490'	15 1/2"	451'	451'
Sand	Water	2265'	2270'	12 1/2"	1096'	1096'
Sandy Lime	Water	2660'	2675'	10"	2701'	2701'
Lime	Water	2910'	2915'	8 1/4"	3182'	3182'
Lime	Water	3505'	3510'	6 5-8"	3428'	3428'
Sandy Lime	Water	3685'	3690'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

~~This~~
3695' to 150' completely filled with mud
150' to 130' Cement Plug.
130' to 30' Filled with mud.
30' to 12' Cement Plug
12' to Top Cellar filled with soil.

PLUGGING
FILE SEC 13 T 11 R 16
BOOK PAGE 2 LINE 33

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes
Was exception made? No. If so describe

Correspondence regarding this well should be addressed to The Palmer Oil Corporation
Address Union National Bank Building, Wichita, Kansas.

STATE OF , COUNTY OF , ss.

 Owner (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Tom Palmer

Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1935

My commission expires Jan. 11, 1936

Tom B. Swan
Notary Public.

TOM PALMER
 UNION NATIONAL BANK BUILDING
 WICHITA, KANSAS

15-051-05701-00-00

CASING RECORD		Location
RUN	LEFT IN HOLE	NE NW NW Sec. 13-11-16W
20		Farm Bowlby #1
15 1/2	471.00"	County Ellis State Kansas
12 1/2	1002.00"	Contractor The Palmer Oil Corporation
10		Commence 8/15/35
8 1/4	221.00"	Completed 10/20/35
6 5/8	2155.00"	Elevation 1897'
5 3/16		

FORMATION	REMARKS	FEET OF STRATA	TOTAL DEPTH
Cellar		15	15
Shale, Light, Soft		10	25
Shale, Dark		10	35
Gumbo		60	95
Shale, Dark, Soft		205	300
Shale, Light, Soft		35	335
Mud		30	365
Red Rock		10	375
Sand		5	380
Shale	(Ran 15" casing 450')	75	455
Red Rock, Soft	(N.T.L. 475-500')	20	465
Sand, White, Soft		35	500
Shale, Blue, Soft		45	545
Sandy Shale, Soft		25	570
Shale, Blue		15	585
Iron & Sand, Hard		15	600
Sandy Shale, Light, Soft		30	630
Shale, Light, Soft		35	665
Lime, White, Hard		10	675
Sandy Lime, White, Hard		20	695
Sandy Shale, Soft	(Ran 12" casing)	42	737
Shale, Light, Soft		3	740
Shale, Sandy, Light, Soft		35	775
Red Rock, Sandy	(Un casing 12")	45	820
Red Rock	(Lowering 12")	254	1074
Lime, Light, Hard		36	1110
Shale, Light, Soft		5	1115
Red Rock		105	1220
Shale, Blue, Soft		40	1260
Red Rock		110	1370
Shale, Blue, Soft		15	1385
Shale, Grey, Soft		75	1460
Salt		215	1675
Shale & Lime Shells		15	1690
Shale, Light, Soft		25	1715
Lime, Broken		15	1730
Lime Shells & Shale		30	1760
Lime, White, Hard		20	1780
Red Rock		25	1805
Lime, Light, Hard		30	1835
Red Rock		30	1865
Lime, Blue, Hard		20	1875
Shale, White, Soft		5	1880
Red Rock		15	1895
Lime, Light, Med.		15	1910
Red Rock		10	1920
Lime, Light		15	1935
Lime, Broken, Med.		50	1985
Shale, Light, Soft		10	1995
Lime, Light, Hard		25	2020
Lime, Sharp, Hard		20	2040
Red Rock, Soft		20	2060
Lime, Hard		15	2075
Red Rock, Soft		20	2095
Lime, Grey, Hard		30	2125
Red Rock, Soft		10	2135
Lime, Light, Hard		30	2165

THE PALMER OIL CORPORATION
 WICHITA, KANSAS
 SEC. 13-11-16W
 PAGE 22

FORMATION	REMARKS	FEET OF STRATA	TOTAL DEPTH
Red Rock, Soft		20	2185
Lime, Light, Hard		5	2190
Red Rock, Soft		15	2205
Lime, Light, Hard		35	2240
Red Rock	(Hole caving 2255')	20	2260
Lime, Light, Hard		5	2265
Sand, Soft	(Water 2265-70) (Running 10")	10	2275
Broken Lime		30	2305
Lime, Light, Hard		20	2325
Shale, Light, Soft		10	2335
Red Rock		10	2345
Shale, Light, Soft		35	2380
Lime, Gray, Broken		45	2425
Shale, Gray		10	2435
Shale, Blue		10	2445
Shale & Lime Shells		23	2468
Lime, Gray, Hard		2	2470
Brown, Shale, Soft		5	2475
Lime, Gray, Hard		8	2483
Shale, Blue		12	2495
Lime, Gray		10	2505
Shale, Blue		10	2515
Lime, Gray		10	2525
Shale, Blue & Shells		50	2575
Red Rock		15	2590
Shale, Blue		90	2680
Lime	(Fighting cave) (Reaming 13")	5	2685
Shale, Blue	(Lowered pipe 2684' 8")	7	2692
Lime, Gray		5	2697
Shale, Gray		3	2700
Lime, Sandy		15	2715
Shale, Blue	(Reamed & lowered pipe 2704' 2")	13	2728
Lime, Gray		17	2745
Shale & Lime Shells		10	2755
Lime, Light, Hard		15	2770
Sandy Shale, Dark		8	2778
Lime, Light, Hard		12	2790
Shale, Blue, Soft		15	2805
Lime, Gray		15	2820
Shale, Blue, Soft		15	2835
Shale, Gray, Hard		5	2840
Shale, Gray, Soft		25	2865
Lime, Gray, Hard		10	2875
Shale, Blue		15	2890
Shale - Shells		15	2905
Lime, Dark, Hard		10	2915
Shale, Blue, Soft	(Running 8" casing)	3	2918
Lime, Gray, Hard	(S.B.M. 2910')	72	2990
Shale, Gray		5	2995
Lime, Brown, Med.		30	3025
Lime, Light, Hard		73	3098
Shale, Blue		4	3102
Lime, Gray		33	3135
Lime, Broken		25	3160
Lime, Light, Hard		10	3170
Shale, Light, Soft	(Caving)	5	3175
Red Rock	(Reamed & lowered pipe 3180')	13	3188
Lime, Gray, Hard		4	3192
Shale, Blue, Soft		18	3210
Various Colored Shale	(S.B.M. 1382')	5	3215
Lime, Light		10	3225
Lime, Brown, Hard		4	3229
Shale, Green, Soft		2	3231
Lime, Light, Med.	(reaming) (Hole dry 3195')	13	3244
Lime, Dark, Hard		7	3251
Lime, Broken		9	3260
Lime, Light, Hard		7	3267
Shale, Blue & Red		5	3272
Lime, Gray		11	3283
Shale, Blue, Soft		3	3286

DRILLING
 THE S.M. 13-11-R 166
 ROCK PAGE 2 LINE 33

FORMATION	REMARKS	FEET OF STRATA	TOTAL DEPTH
Lime, Gray		34	3255
Shale, Blue, Soft		3	3258
Lime, Gray		27	3305
Shale, Blue, Soft		5	3310
Lime, Gray, Hard		12	3322
Lime, Broken		3	3325
Lime, Gray, Hard		25	3350
Shale, Flagged		12	3362
Lime, Gray, Hard		13	3375
Shale, Blue, Soft		10	3385
Lime, Gray, Hard	(Fighting cave)	12	3402
Shale, Blue, Soft		13	3415
Lime, Gray		7	3422
Shale, Blue	(Running 6 5/8" casing)	3	3425
Red Rock		2	3427
Red Rock & Lime Shells		13	3440
Lime, Gray, Hard		13	3453
Shale, Blue, Soft		2	3455
Lime, Gray, Hard		6	3461
Lime, Broken, Soft		34	3495
Conglomerate	(1 B.W.R. 3505-10')	5	3500
Lime & Conglomerate		40	3540
Conglomerate		110	3650
Shale, Broken, Soft		5	3655
Lime, Gray, Hard		7	3662
Shale, Broken, Soft		15	3677
Lime, Gray, Hard	(W.P. . 3685-93')	5	3682
Lime, Broken, Gray		10	3692

Studded hole & pulled 6 5/8", 8", 10", 12" & 15" pipe.

State of Kansas }
County of (leg. let) ss

Mr. Tom Palmer, being first duly sworn on oath states that he is the President of The Palmer Oil Corporation, that as such officer, he is personally familiar with the records of The Palmer Oil Corporation, and that the above well log is a true, correct and accurate copy of the original well log of Well No. 1, Bonity Perm No. 1 of N. 1/4 of Sec. 12-11-16N, Ellis County, Kansas.

Signed Tom Palmer

Attest:

Subscribed and sworn before me this 4th day of November, 1935

My commission expires Jan 11, 1936

Tom Palmer
Notary Public.

