

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

ELLIS County. Sec. 15 Twp. 11S Rge. 16W (#) (W)

Location as "NE/CNW/SW" or footage from lines APPROX. NW NW SW

Lease Owner PETROLEUM, INC.

Lease Name MCGUIRE "F" Well No. 1

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JANUARY 12 19 60

Application for plugging filed JANUARY 11 19 60

Application for plugging approved JANUARY 11 19 60

Plugging commenced JANUARY 11 19 60

Plugging completed JANUARY 12 19 60

Reason for abandonment of well or producing formation
NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, BOX 326, HAYS, KANSAS

Producing formation ----- Depth to top ---- Bottom ---- Total Depth of Well 3492 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 350', FOLLOWED BY A WOODEN PLUG, PLACED 20 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF PLUG, MUDDED UP WITH HEAVY MUD TO 180', FOLLOWED BY A WOODEN PLUG, PLACED 15 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF PLUG, MUDDED UP WITH HEAVY MUD TO 40', FOLLOWED BY A WOODEN PLUG. FILLED HOLE TO BASE OF WELL CELLAR WITH 10 SACKS OF CEMENT.

1-25-1960

CS-1

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY

Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 22ND day of JANUARY, 1960

Arthur J. [Signature] Notary Public.

My commission expires APRIL 14, 1963



WELL LOG 15-051-03748-00-00

COMPANY **PETROLEUM, INCORPORATED**

SEC. 15 T. 11S R. 16W

FARM **MC GUIRE "F" NO. 1**


LOC. **NW, NW, SW**

TOTAL DEPTH **3492'**

COUNTY **ELLIS CO., KANSAS**

COMM. **January 1, 1960** COMP. **January 12, 1960**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 218' W/175 sax.**

ELEVATION **1865' DF**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Surface soil & sand
80	Clay
95	Sand & clay
218	Clay & blue shale
750	Shale
885	Red bed & shale
1045	Red bed
1083=	Anhydrite
1225	Shale & shells
1630	Shale
1815	Lime & shale
2000	Shale & lime
2785	Lime & shale
2925	Lime
3060	Lime & shale
3164	Lime
3210	Lime & shale
3450	Lime
3492	Lime & shale
3492	T. D.

1-25-1960
CORRELATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 MC GUIRE "F" well.

Verne A. Morris

Subscribed and sworn to before me this 20th day of January 19 60

My Commission Expires: April 14, 1963

Arthur J. Willis
NOTARY PUBLIC