

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Donald C. Clark dba CFA Oil Company
 Address: P.O.Box 252, Bonner Springs, KS. 66012
 Phone: (913) 449 - 5292 Operator License #: 34178
 Type of Well: D&A Docket #: N/A
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 10/8/2008 (Date)
 by: Duane Krueger (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 161-20076-00-00
 Lease Name: Sue Duroche Lease Well No. 1 KCCPWT
 Well Number: No. 1
 Spot Location (QQQQ): SE - SE - SW -
330 Feet from North / South Section Line
2970 Feet from East / West Section Line
 Sec. 20 Twp. 10 S. R. 9 East West
 County: Riley
 Date Well Completed: 10/8/08
 Plugging Commenced: 10/8/08
 Plugging Completed: 10/8/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
D&A - Cemented to surface	Surface	surface	174 feet	8 5/8	151 feet Surface Casing	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

D&A - drilled 7 7/8 open hole to 1074 feet, 35 sacks at 1060, 35 sacks at 150, 25 sacks at 60 to surface, plugged and abandoned

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 05 2008

Name of Plugging Contractor: Kan Drill Inc License #: 32548
 Address: 610 East Main, Blue Mound, KS 66010
 CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Donald C Clark dba CFA Oil Company
 State of Kansas County, LV, ss.

Don C. Clark (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Donald C Clark

(Address) Po Box 252 BSK 66012

SUBSCRIBED and SWORN TO before me this 2 day of December, 2008

Guadalupe Ramirez My Commission Expires: 2-19-2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



Handwritten initials



ENTERED

TICKET NUMBER 19516

LOCATION EUREKA

FOREMAN Rick Ledford

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-2-08	3115	Sue Ourchoe #2	20	10	9E	Riley
CUSTOMER LFA OIL Co.			Kan-drill			
MAILING ADDRESS Box 252			TRUCK #	DRIVER	TRUCK #	DRIVER
CITY Bonner Springs			463	Shannon		
STATE KS			439	Calin		
ZIP CODE 66602						

JOB TYPE surface HOLE SIZE 12 1/4" HOLE DEPTH 174' NB. CASING SIZE & WEIGHT 8 5/8"
 CASING DEPTH 151' G.L. DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 15" SLURRY VOL 31 Bbl WATER gal/sk 6.5 CEMENT LEFT in CASING 20'
 DISPLACEMENT 8 1/2 Bbl DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting- Rig up to 8 5/8" casing. Break circulation w/ fresh water
Pump 50 Bbl fresh water ahead to get drilling mud out of hole. Mixed 125
sks regular class "A" cement w/ 370 cact2, 470 gal + 1/2" flaccle @ 15' min.
Displa w/ 8 1/2 Bbl fresh water. shut casing in w/ good cement returns to surface.
7 Bbl slurry to pit. Job complete. Rig down.

"Thank You"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	725.00	725.00
5406	110	MILEAGE	3.65	401.50
11045	125 SKS	regular class "A" cement	13.50	1687.50
1102	350*	370 cact2	.75	262.50
1118A	470*	470 gal	.17	79.90
1107	31*	1/2" flaccle @/sk	2.10	65.10
5407A	5.88	ton-mileage bulk tax	1.20	776.16
RECEIVED KANSAS CORPORATION COMMISSION DEC 05 2008 CONSERVATION DIVISION WICHITA, KS				
			Subtotal	3997.66
			SALES TAX	131.98
			ESTIMATED TOTAL	4129.64

Flavin 3737

206360

AUTHORIZATION Witnessed by Donald Clark

TITLE Co. Rep.

DATE _____



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 226360

Invoice Date: 10/08/2008 Terms:

Page 1

CFA OIL CO
BOX 252
BONNER SPRINGS KS 66012
() -

SUE DUROCHE #1
19516
10-02-08

5% Cash

Part Number	Description	Qty	Unit Price	Total
1104S	CLASS "A" CEMENT (SALE)	125.00	13.5000	1687.50
1102	CALCIUM CHLORIDE (50#)	350.00	.7500	262.50
1118A	S-5 GEL/ BENTONITE (50#)	470.00	.1700	79.90
1107	FLO-SEAL (25#)	31.00	2.1000	65.10

Description	Hours	Unit Price	Total
439 TON MILEAGE DELIVERY	646.80	1.20	776.16
463 CEMENT PUMP (SURFACE)	1.00	725.00	725.00
463 EQUIPMENT MILEAGE (ONE WAY)	110.00	3.65	401.50

*CK 10/18
10/14/08*

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 05 2008

CONSERVATION DIVISION
WICHITA, KS

Parts:	2095.00	Freight:	.00	Tax:	131.98	AR	4129.64
Labor:	.00	Misc:	.00	Total:	4129.64		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____

Date _____

BARTLESVILLE, OK
918/338-0808

ELDORADO, KS
316/322-7022

EUREKA, Ks
620/583-7664

GILLETTE, WY
307/686-4914

McALESTER, OK
918/426-7667

OTTAWA, Ks
785/242-4044

THAYER, Ks
620/839-5289

WORLAND, WY
307/347-4577



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 19555

LOCATION Evans

FOREMAN Rick [unclear]

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-2-08	3115	Sue Ouchoche #2	20	10	08	Butte
CUSTOMER			[REDACTED]			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
CFA OIL CO.			463	Shannon		
Box 252			515	Jarrod		
CITY		STATE	ZIP CODE			
Bonner Springs		KS	66602			

JOB TYPE P.T.A HOLE SIZE 7 7/8" HOLE DEPTH 1024' CASING SIZE & WEIGHT _____
 CASING DEPTH _____ DRILL PIPE 3 1/2" TUBING _____ OTHER _____
 SLURRY WEIGHT 14" SLURRY VOL _____ WATER gal/sk 7.0 CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting Rig 4 to 3 1/2" drill pipe. Plogging orders as follows:

- 35 sacks @ 1000'
- 35 sacks @ 150'
- 25 sacks @ 10' to surface

"Thank You"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5465A	1	PUMP CHARGE	925.00	925.00
5466	110	MILEAGE	3.65	401.50
1121	95 sacks	60/40 Premix cement	11.25	1068.75
1118A	325 gal	472 gal	.17	55.25
5407A	4.09	tan-mileage bank toll	1.20	530.00
RECEIVED KANSAS CORPORATION COMMISSION				
DEC 05 2008				
CONSERVATION DIVISION WICHITA KS				
			3.65	401.50
			SALES TAX	71.31
			ESTIMATED	
			TOTAL	2071.28

Revin 3737

AUTHORIZATION Called by Annie

206494
TITLE Rig Oper

DATE _____



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 226494

Invoice Date: 10/10/2008 Terms:

Page 1

CFA OIL CO
BOX 252
BONNER SPRINGS KS 66012
() -

SUE DUROCHE #1
19555
10-08-08

Cash 590 deposit

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	95.00	11.3500	1078.25
1118A	S-5 GEL/ BENTONITE (50#)	325.00	.1700	55.25

Description	Hours	Unit Price	Total
463 P & A NEW WELL	1.00	925.00	925.00
463 EQUIPMENT MILEAGE (ONE WAY)	110.00	3.65	401.50
515 TON MILEAGE DELIVERY	449.90	1.20	539.88

*CHK# 10/18
10/14/08*

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2008
CONSERVATION DIVISION
WICHITA, KS

Parts:	1133.50	Freight:	.00	Tax:	71.41	AR	3071.29
Labor:	.00	Misc:	.00	Total:	3071.29		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____