

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Grady Bolding Corporation  
Address: P.O. Box 486 Ellinwood, Kansas 67526  
Phone: (620) 564-2240 Operator License #: 7383  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Patrick Staab (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-051-03208-0000  
Lease Name: Wiesner  
Well Number: 5  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - SE  
990 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 13 Twp. 15 S. R. 18  East  West  
County: Ellis  
Date Well Completed: 1961  
Plugging Commenced: 1-22-09  
Plugging Completed: 1-23-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1189'	None
				5-1/2"	3615'	2310'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3300' and 5 sacks cement. Cut casing loose @2310', pulled up to 1650', pumped 160 sxs. cement and 300# hulls, pulled up to 1170', pumped 50 sxs. cement and 100# hulls, pulled up to 540', pumped 50 sxs. cement and 100# hulls, pulled up to 150' and circulatead 50 sxs. cement to surface. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529  
Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Grady Bolding Corporation

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 20th day of February, 2009

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_  
NOTARY PUBLIC - State of Kansas  
IRENE HERZBERG  
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS CORPORATION COMMISSION

FEB 25 2009

RECEIVED

[Handwritten initials]