

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John J. Darrah
Address: 225 N. Market #300 Wichita, Kansas 67202
Phone: (316) 786-4046 Operator License #: 5088
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 053-00630 - 00-00
Lease Name: Vacke B KCC PET Per CP2/3
Vacke
Well Number: _____
Spot Location (QQQQ): _____ - SW - NE - NE
4280 Feet from North / South Section Line
1170 Feet from East / West Section Line
Sec. 5 Twp. 16 S. R. 10 East West
County: Ellsworth
Date Well Completed: _____
Plugging Commenced: 2-6-09
Plugging Completed: 2-10-09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | 8-5/8" | 307 | None |
| | | | | 5-1/2" | 3366 | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3240' and 5 sxs. cement. Perforated casing @1300', 1000' and 350'. Ran tubing to 1300', pumped 35 sxs.

cement, pulled up to 1000', pumped 35 sxs. cement, pulled up to 350' and circulated 185 sxs. cement to surface.

60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

KANSAS CORPORATION COMMISSION

FEB 25 2009

Name of Party Responsible for Plugging Fees: John J. Darrah
State of Kansas County, Rice, ss.

RECEIVED

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 20th day of February, 2009

Irene Herzberg
Notary Public

My Commission Expires: _____
NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

107