

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gore Oil Company  
Address: P.O. Box 2757, Wichita, KS 67201-2757  
Phone: (316) 263-3535 Operator License #: 5552  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 3-26-08 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Leavenworth Depth to Top: 4026' Bottom: 4028' T.D. \_\_\_\_\_  
L-KC Depth to Top: 4077' Bottom: 4350' T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-153-20,692-00-00  
Lease Name: Burch-Savage *CP213*  
Well Number: 1 *KCC Pkt Per RBDm*  
Spot Location (QQQQ): E2 - NE - NE - *KCC Pkt Per RBDm*  
4620 Feet from  North /  South Section Line  
300 Feet from  East /  West Section Line  
Sec. 14 Twp. 1 S. R. 35  East  West  
County: Rawlins  
Date Well Completed: 10-22-87  
Plugging Commenced: 3-31-08  
Plugging Completed: 3-31-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil, Water	0'	305'	8 5/8"	305'	0'
Production	Oil, Water	0'	4352'	5 1/2"	4352'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 3700', pumped 50 sx cmt w/300# hulls. Pulled tbg to 3040', pumped 30 sx gel, gel to surface. Pulled tbg to 350', pumped 80 sx cmt, cmt to surface. Pulled tbg to surface. Connected to 5 1/2" production csg, pumped 5 sx cmt. Connected to 8 5/8" surface pipe, pumped 40 sx cmt. Max psi 375#, SIP 0#.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606  
Address: 250 N. Water, Suite 300, Wichita, KS 67202  
Name of Party Responsible for Plugging Fees: Gore Oil Company  
State of Kansas County, Sedgwick, ss.  
Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 24 2009  
CONSERVATION DIVISION  
WICHITA, KS

REBECCA K. CRAWFORD  
State of Kansas  
My Appt. Exp. 3-20-11

(Signature) Larry M. Jack  
(Address) Wichita, KS  
SUBSCRIBED and SWORN TO before me this 23rd day of February, 20 09  
Rebecca K. Crawford My Commission Expires: 3-20-11  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PK*