

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-167-00414-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 37-13

LOCATION SE-SE-SE

SEC. 4 TWP. 11 RGE. 12W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease A.P.J. Steinle

Operator Russell Supply Company. Address Box 25. Russell, Kansas.

Field _____ County Russell.

Total Depth 3140' Feet.

Plugging Contractor Arnett Casing Pulling Company.

Plugging Contractor's License No. 265

Address Hoisington, Kansas.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 12" @ 66' No Cem. Record.. 7" @ 3140' cem. 75 sx. .

Run measuring line and found bridge @ 2107', set plug, chat and 6 sx. cem.

with dump bailer. Shot 7" pipe off @ 1000' and pulled up to 770' and pumped

in 35 sx. of jell mud. Then pulled 7" pipe up to 310' from top, and pumped

in 50 sx. cem.. Pulled pipe out. Bailed light fluid off and mud to 80'

from top, set plug, rock bridge and 35 sx. cem. to base of cellar.

Halliburton pumped in mud and the 50 sx. cem. for fresh water plug.

Milton Galyard
District Conservation Agent

Date 9-5-57

09-11-1957

PLUGGING
FILE SEC 4 T. 11 R. 12W
BOOK PAGE 37 LINE 13