

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,845-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Shields Oil Producers Inc.

Complete Address Shields Bldg. Russell, Ks. 67665

Lease Name Strecker Well-No. 1

Location NE NE NW Sec. 31 Twp. 11 Rge. 12 (East) (West)

County Russell Total Depth 3455'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Shields Oil Producers Inc.

Address Shields Bldg. Russell, Ks. License No. _____

Operation Completed: Hour: 5:00 AM Day: 7 Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All Part None XXX

The above well was plugged as follows:

8 5/8" 270' S.P. cuc. W/ 160 sacks common 2% Gel- ~~3~~ % Cal.Cl.

Ordered 135 sacks 50/50 posmix 4% Gel-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 690' W/ 70 sacks cement

2nd plug @ 270' W/ 50 sacks cement

3rd plug solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks cement in rat hole, and 5 sacks cement in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1982
CONSERVATION DIVISION

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

RECEIVED
2-9-82
9361-W