

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 106-14
LOCATION NW-NW-NE
SEC. 4 TWP. 11 RGE. 15 W

15-167-00286-00-00

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Worley
Operator Western Development Co. - Del. Address Box 1201, Santa Fe, N.M.
Field _____ County Russell
Total Depth 3421 Feet.
Plugging Contractor R E D. Casing Pulling Co.
Plugging Contractor's License No. 236
Address Ellinwood Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 985' c.w.c. 5 1/2" set 3420' w/ 165 st Cem.
Present T.D. 3368' top Ref 3198'. Sanded hole to
3180' and dumped 5 st Cem. Shot off and pulled
5 1/2" Oil string. Filled hole with mud to 240'
Set rock bridge and dumped 20 st Cem. with
dump bailer. Mud to 35' rock bridge and
10 st Cem. to base of cellar.

Warren H. Horner
District Conservation Agent
Date Mar. 28, 1955

RECEIVED
STATE CORPORATION COMMISSION
APR - 1 1955
04-01-1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 4 T 11 R 15 W
BOOK PAGE 106 LINE 14