

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Biting Building
Wichita, Kansas

15-167-03895-00-00

FILE NO. _____

LOCATION SW SE SW

SEC. 4 TWP. 11 RGE. 15

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Worley

Operator Birmingham-Bartlett Address Wichita, Kans

Field Fairport County Russell

Total Depth 3410 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 172' circulated with cement - 5 1/8" at 3372' with
75 sax cement behind.

Sand to 3365', run 4 sax cement with dump bailer, pulled
2650' of 5 1/2", filled hole with heavy mud to 170', set wood
plug, rock bridge and 15 sax cement - filled with heavy mud to
35', set wood plug, rock and 10 sax cement to bottom cellar.

02-23-1950
FEB 28 1950

Edward L. ...
District Conservation Agent

Date 2-20-50

PLUGGING
FILE SEC. 4 T. 11 R. 15
BOOK PAGE 139 LINE 41