

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

DEC 2 1974  
12-02-1974  
CONSERVATION DIVISION  
Wichita, Kansas

15-167-20709-00-00

Operator's Full Name Vincent Oil Corporation

Complete Address 719 Union Center Bldg., Wichita, Kansas

Lease Name Hackmeister Well No. # 1

Location RXXXX W/2 SW SW Sec. 4 Twp. 11 Rge. 15 (E) (W)W

County Russell Total Depth 3410

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Woodman & Iannitti Drilling Company

Address 1008 Union Nat'l Bldg., Wichita, License No. \_\_\_\_\_

Operation Completed: Hour 10:30 P.M. Day 30 Month 11 Year 1974

The above well was plugged as follows:

8 5/8" csg. 207' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 40 sax cement thru  
drill pipe. Mud to 200' & displaced 25 sax cement thru drill pipe. Mud to 40', XXX XXX  
1/2 sax hulls, plug, & displaced 10 sax cement with Sun Cementing Company's pump  
truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Dave Leonard  
Well Plugging Supervisor

DATE 12/4/74

INV. NO. 415W