

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-167-00254-00-00

FILE NO. 140-17

LOCATION NW NW SW

SEC. 15 TWP. 11 RGE. 15

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Reich

Operator Aylward Drg Co Address Wichita, Kans

Field Fairport County Russell

Total Depth 3423 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 120' circulated with cement - 5 1/2" at ~~3423~~ 3384'  
with 75 sax cement behind.

Chat to 3380', run 5 sax cement with dump bailer - pulled  
2900' of 5 1/2". filled hole with heavy mud to 150', set rock  
bridge and 15 sax cement, filled hole with heavy mud to 35',  
set rock bridge and 10 sax cement to bottom cellar.

*J. P. Perry*  
District Conservation Agent

Date 3-8-50 05-09-1950

**PLUGGING**  
FILE SEC-15T-11-R15W  
BOOK PAGE 140 LINE 17