

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

STATE CORPORATION COMMISSION  
3-15-65  
MAR 15 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co., has this  
date requested permission to plug the following described well:

Mr. Helberg. guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Ks.

Lease Name: Everette Keith Well No. 1

Location: CS/2-SE-SW Sec. 1 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3905<sup>18 27 fca</sup> Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

174'--8 5/8" Surface pipe, cement circulated with 85 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	180' with 1/4 sk. hulls &
		20 Sx. cement.
"	"	40' with 1/2 sk. hulls &
		10 Sx. cement.

Very truly yours,

M. L. Nichols  
Conservation Division Agent