



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Derrick American Oil, Incorporated,

Complete Address: 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name: Knobel Well No. 2

Location: CNE Sec. 17 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4112' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 1150'.

Circulate hole with heavy mud, pull DP to 1375' and displace 100 Sx. cement  
thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP. Pull DP, set  
plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*A. L. Fehel*  
Conservation Division Agent