



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: Martin Well No. 1

Location: 440' FNL & 440' FWL of SE/4 Sec. 17 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4140' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

239'--8 5/8 " Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1150'.

Circulate hole with heavy mud. Pull DP to 1375' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent