



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
6-26-1972
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lyle Hicks of Dreiling Oil, Inc. has this
date requested permission to plug the following described well:

Mr. John P. Jennings guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation

Complete Address: Suite 1000, Century Plaza, Wichita, Kansas 67202

Lease Name: Stecklein Well No. # 1

Location: SW NW SW Sec. 34 Twp. 11 Rge. 18 (E)(W) W

County: Ellis Total Depth 3700 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lyle Hicks was instructed to plug the well as follows:

8 5/8" csg. 229' Cwc.

Circulated hole with heavy mud to 700', set plug, & displaced 70 sax

cement thru drill pipe. Mud to 220' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Halliburton Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

Don Lusk
Conservation Division Agent