

State of Kansas



15-051-20503-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1969
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Geritzen of H-30 Drlg/ has this date requested permission to plug the following described well:

Mr. Geritzen guarantees payment of the plugging fee.

Operator's full Name: HUMMON Oil, Inc.

Complete Address: 821 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Stecklein Well No. 1

Location: C NE SE SW Sec. 34 Twp. 11 Rge. (E)(W) 18W

County: Ellis Total Depth 3701 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Geritzen was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Messerly
Conservation Division Agent