



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
1-5-1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Davis of Hellar Drlg. has this
date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie & Maderia Oil Co.

Complete Address: 412 Union Center Bldg., Wichita, Ks.

Lease Name: Meistrell "A" Well No. 1

Location: SE SE SW Sec. 10 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3177 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Davis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 420' and displace
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent