

Operator Name: CMX, Inc. Lease Name: Catlin Well #: 1-35
 Sec. 35 Twp. 31 S. R. 13 East West County: Barber

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)
 List All E. Logs Run:

CDNL, DIL, CBL.

<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Name	Top	Datum
Heebner	3562	-1977
Lwr Doug. Sand	3698	-2113
Stark Shale	4081	-2496
Hush Shale	4122	-2537
Mississippi	4240	-2655
Kinderhook Shale	4408	-2833
RTD	4450	-2865

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	24#	374'	60/40 Pozmix	300	3% cc 2% gel
Production	7 7/8	4 1/2	10.5#	4449'	Class H	225	10% gyp seal, 10% salt, 6# Kol seal

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4198'-4202'	2500 gallons of MCA acid.	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2 3/8"	4220'		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.			Producing Method		
1/6/06			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	20				

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)
 METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____
 Production Interval _____

RECEIVED
FEB 10 2006
KCC WICHITA

CONFIDENTIAL
 FEB 09 2006
 KCC

ALLIED CEMENTING CO., INC. 20999

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Med. Lodge KS

DATE <u>31 Oct 05</u>	SEC. <u>35</u>	TWP. <u>3 1/2</u>	RANGE <u>13 W</u>	CALLED OUT <u>08:30 AM</u>	ON LOCATION <u>09:30 AM</u>	JOB START <u>2:20 PM</u>	JOB FINISH <u>10:50 PM</u>
LEASE <u>Catt/In</u>		WELL # <u>1-35</u>	LOCATION <u>Med. Lodge, KS, 2 1/2 W, 1 N, 1/2</u>		COUNTY <u>Barber</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			<u>N, 1/4 N, 1/2 W, 1/2 N, w/into</u>				

CONTRACTOR Fossil Delg. OWNER CMX inc
 TYPE OF JOB Production Casing
 HOLE SIZE 7 7/8 T.D. 4450
 CASING SIZE 4 1/2 DEPTH 4453
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX 1200 MINIMUM 200
 MEAS. LINE SHOE JOINT 42
 CEMENT LEFT IN CSG. 42'
 PERFS.
 DISPLACEMENT Bbls, 2% KCL H²O

CEMENT

AMOUNT ORDERED 25 x 60:40 6% gcl and 200 x H + 10% gyp + 10% salt + 6# Kol seal + 6% FL160 + .8% gas Block Cla Pro 14 gls.
1000 gal mud clean 1000 gls Mud Clean C

COMMON	<u>15</u>	<u>A</u>	@	<u>8.70</u>	<u>130.50</u>
POZMIX	<u>10</u>		@	<u>4.70</u>	<u>47.00</u>
GEL	<u>1</u>		@	<u>14.00</u>	<u>14.00</u>
CHLORIDE			@		
ASE	<u>200</u>	<u>"H"</u>	@	<u>10.50</u>	<u>2100.00</u>
Mud Clean	<u>1000 g</u>		@	<u>1.00</u>	<u>1000.00</u>
Mud Clean C	<u>1000 gl.</u>		@	<u>1.25</u>	<u>1250.00</u>
Cla Pro	<u>14 gls.</u>		@	<u>24.10</u>	<u>337.40</u>
Gyp Seal	<u>19</u>		@	<u>19.15</u>	<u>363.85</u>
Salt	<u>22</u>		@	<u>7.90</u>	<u>173.80</u>
Kol Seal	<u>1200 #</u>		@	<u>.60</u>	<u>720.00</u>
FL-160	<u>150 #</u>		@	<u>8.70</u>	<u>1305.00</u>
Gas Block	<u>150 #</u>		@	<u>7.40</u>	<u>1110.00</u>
HANDLING	<u>297</u>		@	<u>1.60</u>	<u>475.20</u>
MILEAGE	<u>6 x 297 x .06</u>				<u>180.00</u>
Min chg:					<u>TOTAL 9206.75</u>

EQUIPMENT

PUMP TRUCK CEMENTER Dr. Felix
 # 397 HELPER C. Reed
 BULK TRUCK
 # 364 DRIVER L. Freeman Jr.
 BULK TRUCK
 # DRIVER

REMARKS:

Pipe on Bottom, Break Circ. Pump 500gal mud Clean
"C" Pump 500gal mud Clean, Plug Rat & mouse hole,
Pump 100 sx "H" + 10% gyp + 10% salt + 6# Kol seal +
.6% FL160 + .8% gas Block, shut down wash pump
& lines, Release Plug, Start Disp. Shot down at
7 2/4 Bbls 2% KCL water, Circ. mud Pump 500gal
mud Clean "C", 500gal mud Clean, Pump 100 sx lead cement
stop, wash, Release, Start disp. Slow rate at 60
Bbls., Bung Plug to 1200PSI at 7 1/4 Bbls ~~2%~~ 2%
KCL H²O, Release PSI, Float did hold,
 CHARGE TO: CMX inc.

SERVICE

DEPTH OF JOB	<u>4453</u>		
PUMP TRUCK CHARGE			<u>1370.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>6</u>	@	<u>5.00 30.00</u>
MANIFOLD headrent		@	<u>75.00 75.00</u>
<u>6 Hrs. standby time</u>		@	<u>140.00 840.00</u>

RECEIVED

FEB 10 2006

TOTAL 2315.00

KCC WICHITA

PLUG & FLOAT EQUIPMENT

<u>1-AFU Float Sbr</u>	@	<u>200.00</u>	<u>200.00</u>
<u>2-Latch down Plug Assys.</u>	@	<u>300.00</u>	<u>600.00</u>
<u>3-centralizers</u>	@	<u>45.00</u>	<u>225.00</u>
<u>1-Basket</u>	@	<u>116.00</u>	<u>116.00</u>
	@		

TOTAL 1141.00

TAX _____
 TOTAL CHARGE ~~2315.00~~
 DISCOUNT ~~1141.00~~ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE x Ken LeBlanc

x Ken LeBlanc
 PRINTED NAME

4 1/2"

ALLIED CEMENTING CO., INC.

23231

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <i>10-19-05</i>	SEC. <i>35</i>	TWP. <i>315</i>	RANGE <i>13W</i>	CALLED OUT <i>6:00 AM</i>	ON LOCATION <i>7:30 AM</i>	JOB START <i>12:00 PM</i>	JOB FINISH <i>12:30 PM</i>
LEASE <i>Cattlin</i>		WELL # <i>1-35</i>	LOCATION <i>Med. Lodge 2 1/2 mi. to Redwell Barber</i>		COUNTY <i>Barber</i>	STATE <i>KS.</i>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)			Feeders sign 1 1/2, 1 1/4, 1 1/2, 1 1/4, 1 1/2, 1 1/4 w/s				

CONTRACTOR *Fossil Drilling*

TYPE OF JOB *Surface*

HOLE SIZE *12 1/4* T.D.

CASING SIZE *8 7/8* DEPTH *374'*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX *250* MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT *22 3/4 Bbls freshwater*

OWNER *CMX, INC.*

CEMENT AMOUNT ORDERED *300 sx 60:40:2 + 3% cc*

EQUIPMENT

PUMP TRUCK CEMENTER *Carl Bolding*

32 HELPER *Travy Cushenbery*

BULK TRUCK DRIVER *Steve Kramer*

364 DRIVER

BULK TRUCK DRIVER

COMMON	<i>180</i>	A	@	<i>8.70</i>	<i>1566.00</i>
POZMIX	<i>120</i>		@	<i>4.70</i>	<i>564.00</i>
GEL	<i>5</i>		@	<i>14.00</i>	<i>70.00</i>
CHLORIDE	<i>10</i>		@	<i>38.00</i>	<i>380.00</i>
ASC			@		
HANDLING	<i>315</i>		@	<i>1.60</i>	<i>504.00</i>
MILEAGE	<i>6 x 315</i>	X	@	<i>.06</i>	<i>180.00</i>
<i>Min chgs</i>					TOTAL <i>3264.00</i>

REMARKS:

Run 374' 8 7/8 Csg
Break Circulation w/ Rig.
Mix 300 sx 60:40:2 + 3% cc
Release plug + Displace with
22 3/4 Bbls water
Leave 15' cement in pipe + shut in
circulate 50 sx to Pit

SERVICE

DEPTH OF JOB	<i>374'</i>			
PUMP TRUCK CHARGE	<i>0-300'</i>			<i>670.00</i>
EXTRA FOOTAGE	<i>74'</i>	@	<i>.55</i>	<i>40.70</i>
MILEAGE	<i>6</i>	@	<i>5.00</i>	<i>30.00</i>
MANIFOLD		@		
<i>Head Rental</i>		@	<i>75.00</i>	<i>75.00</i>

RECEIVED

FEB 10 2006

TOTAL *815.70*

CHARGE TO: *CMX, INC.*

STREET _____

CITY _____ STATE _____ ZIP _____

KCC WICHITA
8/8 PLUG & FLOAT EQUIPMENT

<i>1 TWP</i>	@	<i>55.00</i>	<i>55.00</i>
	@		
	@		
	@		
	@		

CONFIDENTIAL

FEB 10 2006

TOTAL *55.00*

TAX	<i>KCC</i>		
TOTAL CHARGE	_____		
DISCOUNT	_____	IF PAID IN 30 DAYS	

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE *[Signature]*

PRINTED NAME