


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County. Sec. 30 Twp. 11 Rge. 17 (W) W (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW SE SW
Lease Owner The El Dorado Refining Company Etal.
Lease Name PEAVY Well No. 1
Office Address Box 551, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-31-1949
Application for plugging filed 8-25-1951
Application for plugging approved 9-5-1951
Plugging commenced 9-26-1951
Plugging completed 10-2-1951
Reason for abandonment of well or producing formation
Productivity Exhausted
If a producing well is abandoned, date of last production 8-27-1951
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well - Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3696' Bottom 3663' Total Depth of Well 3663' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1358'	0000'
				5 1/2"	3637'	3071.30'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3658' to 3625' -
Run 4 sacks of cement at 3625' - Mudded to 300'
Set bridge and rock to 290' - run 15 sacks of cement
at 290' - mudded to 30' 0 run 10 sacks of cement
to cap.

RECEIVED
STATE CORPORATION COMMISSION
10-18-1951
OCT 18 1951

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to The El Dorado Refining Company
Address Box 209 - Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Levi B. Sherman (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman
Box 209 - Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of October, 1951.

Herbert B. Parson
Notary Public.

My commission expires 8-13-55

PLUGGING
FILE SEC 30 T 11 R 170
BOOK PAGE 107 LINE 38

STERLING DRILLING COMPANY 15-051-04827-00-00

STERLING, KANSAS

WELL LOG ----- PEAVEY #1

Location - C NW/4 SE/4 SW/4 of Section 30-11S-17W, Ellis County, Kansas.

Owner - The Eldorado Refining Company
Contractor - Sterling Drilling Company

Commenced - 12-30-49
Completed - 1-15-50

Total Depth - 3641' (w/r)

LOG

0- 70 Clay
70-1360 Shale & Shells
1360-1361 Shale
1361-1400 Anhydrite
1400-1630 Shale & Shells
1630-1900 Shale
1900-2355 Shale & Lime
2355-2520 Lime
2520-2605 Lime & Shale
2605-2645 Lime
2645-2670 Shale & Lime
2670-2760 Lime
2760-2945 Lime & Shale
2945-3620 Lime
3620-3641 Shale

3663 T. D. P. B. 3657

FORMATION TOPS:

Anhy. 1361
Heebner 3316
Lans. 3355
Arch Simp. 3617
Arb. 3636

CASING RECORD

1375 Feet 8-5/8" Surface Pipe
Cemented with 550 Sacks Cement

3641 Feet 5 1/2" O.D. Casing
Cemented with 75 Sacks Cement

PRODUCTION

93 BOPD, N.W.

FILED IN
FILE SEC-30 T-11 R-17W
BOOK PAGE 107 LINE 38

Good odor & good S.F.O. @ 3636

DP & DD 3639, N. S.

DD 3658, 175' OIH/13 hrs.

DD 3663, 500' WEH 3660-63

~~DD 3657, 500' acid, 800' OIH/12 hrs. § 2 1/2-3 BOPH, N. W.~~

P. B. 3657, 500 acid, 800' OIH/12 hrs. § 2 1/2-3 BOPH, N. W.

~~DD 3657, 1500 acid, 500' OIH/12 hrs. § 3 BOPH/6 hrs.~~

NOV-3-1951
NOV-8-1951
Wichita, Kansas