

15-051-05298-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NONE

LEASE NAME PEAVEY

WELL NUMBER 2 (SE SW SW)

330 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 30 TWP. 11 RGE. 17 (X) or (W)

COUNTY Ellis

Date Well Completed 11-25-53

Plugging Commenced 5-4-87

Plugging Completed 5-4-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR WALTERS DRILLING CO., INC.

ADDRESS 100 S. Main, Suite 420 -Wichita, Ks. 67202

PHONE# (316) 265-6683 OPERATORS LICENSE NO. 5076

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS, KANSAS

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation Arbuckle-LansingKC Depth to Top 3630 Bottom ? T.D. 3655

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	182	8-5/8	182	NONE
Arbuckle		0	3654		3654	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

(SEE BACK)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor WALTERS DRILLING CO., INC. License # 5076

Address 100 S. Main - Suite 420 - Wichita, Kansas 67202


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

ROBERT F. WALTERS (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert F. Walters

(Address) 100 S. Main #420-Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 87



Linda L. Rushton
Linda L. Rushton Notary Public

My Commission Expires: 10-14-89

On May 4, 1987 Allied Cementing Co, Inc. hooked up pump truck to annular space between 8-5/8" surface pipe and 5-1/2" oil string casing. A total of 5 sacks of cement were pumped down the annular space with a pressure of 350 psi. Allied hooked up to 5-1/2" casing, loaded casing and pumped saltwater at the rate of 3 barrels per minute at 600 psi to establish that cement would move down the pipe. Then mixed ten sacks of common cement and 400 pounds of hulls followed by 185 sacks of cement with 1 sack of hulls and pumped cement down the casing.---Maximum pressure was 1,500 psi and the well was shut in at 1,500 psi at 4:45 p.m. May 4, 1987.

ALLIED CEMENTING CO.
P.O. BOX 100
DALLAS, TEXAS 75201
TELEPHONE 714-351-1111