

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER _____

LEASE NAME Hall

WELL NUMBER # 2

SPOT LOCATION NE-SE-NE

SEC. 35 TWP. 11S RGE. 17 (E) OR (W)

COUNTY ELLIS

DATE WELL COMPLETED 9-25-69

PLUGGING COMMENCED 7-16-84

PLUGGING COMPLETED 7-16-84

LEASE OPERATOR ENERGY SOURCES INC.

ADDRESS 250 Willow Hill Centre
4413 82nd St. Suburban Texas 79424

PHONE # (806) 794-9444 OPERATORS LICENSE NO. 8328

CHARACTER OF WELL Oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? HAYS Kans.

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Arb. DEPTH TO TOP 3597 BOTTOM 3660 T.D. 3660'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Arb</u>	<u>oil</u>	<u>3597</u>	<u>3660</u>	<u>8 5/8"</u>	<u>236</u>	<u>NONE</u>
<u>L-Kans. City</u>	<u>oil</u>	<u>3391</u>	<u>3547</u>	<u>5 1/2"</u>	<u>3642'</u>	<u>NONE</u>
		<u>3331</u>	<u>3547</u>			

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Dakota broke in at 990' casing at this point was eaten up. Re plug got stuck at 1032' we attempted to fish out. But went out of pipe at 1032' down to 1042' in Red bed formations at this point we acquired 1500# under packer set at 935 to 2000# standing press. Drilled breakout to 1042' still went out of pipe. Called State pluggers at this point and plugged well on 7-16-84 with 125ccs Pumped 300# down 8 5/8" casing broke head to 500# pumped 95cc down. 5 1/2" casing standing press 200# witnessed by State pluggers.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Plainville Well Service Co. LICENSE No. _____
ADDRESS Plainville Well Service

STATE OF KANSAS COUNTY OF ELLIS, SS.

Jackie Bell (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Mervin Sullivan

(ADDRESS) _____

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6 DAY OF August, 1984

Larry Langhans
NOTARY PUBLIC

MY COMMISSION EXPIRES: 1/28/87

RECEIVED
STATE CORPORATION COMMISSION
8-10-1984
AUG 10 1984
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83