

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County. Sec. 35 Twp. 11 Rge. (E) 17 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 1320 S. 990 E. From N/4 corner

Lease Owner Cities Service Oil Company

Lease Name Hall

Well No. 1C

Office Address Bartlesville, Oklahoma

Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole

Date, well completed July 2 1938

Application for plugging filed July 2 1938

Application for plugging approved July 2 1938

Plugging Commenced July 2 1938

Plugging Completed July 5 1938

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Shiel

Producing formation Siliceous Depth to top 3637 Bottom 3675 Total Depth of Well 3675 Feet.

Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Siliceous	Dry	3637'	3675'	15 1/2" 10"	97' 1282'	None None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 1200', set 10" wood plug @ 1200' and cemented with 10 sacks, filled with heavy mud to 15' below floor, set wood plug at 10' and cemented with 5 sacks, filled to surface.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Cities Service Oil Co.

Address Attention: Mr. M. M. Mahaffey, Eldorado, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

J. A. Cleverley (employee of owner) or ~~owner or operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Cities Service Oil Co., Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 18 day of July, 1938

My commission expires

Notary Public.

WELL RECORD

Company **Cities Service Oil** No. **1-C** Farm **Hall**

Location **1320th - 910th of 1/4 Cor.** Sec **35** T **11** R **277**

Elevation _____ County **Ellis** State **Kansas**

Date Commenced: **6-11-38**

Date Completed: **7-1-38**

Initial Production **D. & A.**

Drid. by **J.H. Mabey** T.D. **5675'**

Casing Record:

15 1/2" 97' Cor. w/ 100 cks.
10 5/8" 1292' Cor. w/ 650 cks.

Formation:	Depth:
rock and shale	63
shale & shells	300
shale, shells & sand	1000
red bed & shells, sand	1230
red bed, shale	1278
anhydrite	1310
red bed, shale & shells	1407
red bed and shale	1509
red bed & shale & salt	1835
shale & salt	1855
lime & shale	2600
shale & shells	2900
lime & shale	2969
shale	3004
lime	3032
lime broken	3081
lime	3501
lime & shale	3605
cherty conglomerate	3622
Top Erosional Arbuckle	3623
Top Solid Arbuckle	3637
Chert and lime	3670 T.D.

Top Anhydrite	1278
Top Conglomerate	3370
Top Erosional Sil.	3623
Top Solid Sil.	3637
Pen.	383'
T.D.	3675'

Cyfo Record:

75'	0
500'	0
1120'	0
1500'	0
2000'	0
2300'	0
3000'	1 degree

