

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-04910-00-00

API NUMBER ~~XXXX~~ 10-15-46
 LEASE NAME Hall J
 WELL NUMBER #3

TYPE OR PRINT

NOTICE: Fill out completely and return 4290' ft. from S Section Line
 to Cons. Div. office within 30 days. 400' ft. from E Section Line

LEASE OPERATOR OXY USA INC.
 ADDRESS P.O. Box D, Plainville, KS 67663
 PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447

Spot Location - - -
 SEC 32 TWP 11 S RGE 17 or (W)
 COUNTY Ellis

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply)

Date Well Completed 10-15-66 ⁴⁶ ^{ES}
 Plugging Commenced 9-10-97 ^{12/21/08}
 Plugging Completed 9-10-97

The plugging proposal was approved on Dec. 4 1996 (date)
 by David Williams (KCC District Agent's Name)

Is ACO-1 filed? ON FILE If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3590' Bottom 3600' T.D. 3637'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
		5'	1135'	8-5/8"	1135'	0'
		0'	3637'	5-1/2"	3637'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

*** See back for details ***

(If additional description is necessary, use BACK of this form)
 Name of Plugging Contractor Allied Cementing License No. 1-27-1998
 Address Russell, KS NA 1998
 JAN 27 1998

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.
 STATE OF Kansas COUNTY OF Rooks, ss.
 J.D. Hininger (Employee of Operator) or (Operator) of above-described well, being first duly sworn

on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger
 (Address) P.O. Box D, Plainville, Ks 67663

SUBSCRIBED AND SWORN TO before me this 26th day of January 1998

Sheryln Axelson Notary Public

My Commission Expires:
 5-20-2000



15-051-04910-00-00

09/10/97 JOB: Plug and Abandon; CMIC: JD Hininger

P&A - Rigged up and ran 2 7/8 tbg. open ended to 2745' - 8 5/8" mixed and pumped 100 sks. 60/40 cement w/10% gel w/200 lbs. hulls - shut in w/200 psi. - Mixed and pumped dn tbg. w/110 sks w/200 lbs. hulls - pulled tbg. to 1200' - Mixed and pumped 90 sks. w/100 lbs. hulls and circulated cement to surface - Pulled tbg. - Finished filling 5 1/2" to surface w/20 sks. - Plugged @ 1:00 P.M. 9/9/97 - State witness Dennis

Hamel

L/E \$ 594; MAT \$ 3203; CUM: L/E \$ 594, MAT \$ 3203;

HALL S

RECEIVED
STATE OF
1-27-1998
JAN 27 1998