


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-05306-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County. Sec. 35 Twp. 11S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SE/SE/SW
Lease Owner Forbes Casing Pulling Co.
Lease Name Hall Well No. B-2
Office Address P.O. Box 221, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 12-24-1951
Application for plugging filed 12-28-1955
Application for plugging approved 12-29-1955
Plugging commenced 12-29-1955
Plugging completed 1-3-1956
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 8-2-1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3590 Bottom Total Depth of Well 3599 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging started 12-29-55 and completed 1-3-56. Measured in to TD 3599'.


Shot casing off at 2630' and pulled pipe out of hole. Plugged well as follows:
Filled hole with heavy mud to 300', set 10' permanent rock bridge; and dumped in 20 sacks of cement. Filled hole with heavy mud to 40' of top, set 10' permanent rock bridge, and dumped in 10 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. FORBES d/b/a FORBES CASING PULLING CO.
Address P. O. BOX 221, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. O. FORBES (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. O. Forbes*
P.O. BOX 221, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of JANUARY 19 56
My commission expires 1-17-59
Jean Grobe
Notary Public.



PLUGGING
FILE NO. 35-11-R-17
BOOK PAGE 27 LINE 25

DRILLER'S LOG

Jarbes Casing Pulling Co. (original record)

Company: Anderson-Prichard Oil Corp.

SE/4 SE/4 SW/4
Sec. 35, Twp. 11S, Rge. 17W,

Farm: Hall "B" Well No. 2

Total Depth: 3595'

County: Ellis,
Kansas

Comm: 10-25-51 Comp: 11-8-51

Contractor: Glenn W. Peel

Elevation:

Casing:

8 5/8" 1293' cem.
5 1/2" 3591' cem.

Production:

Figures below indicate bottom of formations

Surface Clay	0 -	30
Shale		100
Shale & Shells		1280
Anhydrite		1330
Shells		1400
Shale & Shells		1970
Lime		1995
Lime & Shale		2880
Shale		3000
Shale & Shells		3100
Shale & Lime		3180
Lime		3595
Total Depth		3595

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEEL

BY: *Wm Herbert*

SUBSCRIBED AND SWORN to before me this 14th day of November, 1951.

My commission expires June 4, 1955 *Marion M. Herbert*
Notary Public

PLUGGING
FILE SEC 35 T 11 R 17W
PAGE 27 LINE 3525

RECEIVED
STATE COMMISSION
1-10-1956
JAN 10 1956
CONSERVATION DIVISION
Wichita, Kansas