

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-01169-00-00

WELL PLUGGING RECORD

Ellis

County. Sec. 24 Twp. 11S Rge. 19W (X) (W)

Location as "NE/CNW/SW" or footage from lines NW SE NE

Lease Owner Mayfield-Smith Drilling, Inc.

Lease Name Metz Well No. 1

Office Address 227 Union Center Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 5, 1962 19

Application for plugging filed April 5, 1962 19

Application for plugging approved April 5, 1962 19

Plugging commenced April 5, 1962 19

Plugging completed April 5, 1962 19

Reason for abandonment of well or producing formation

Oil in commercial quantities not found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford County, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3652 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 550' with heavy rotary mud.

Set #1 Plug at 550' with 3 Gals. Hulls, 15 Sks. Cement

Set #2 Plug at 195' with 3 Gals. Hulls, 15 Sks. Cement

Top plug set at 40' with 3 Gals. Hulls, cement to bottom of cellar.

RECEIVED  
STATE OF KANSAS  
4-10-1962  
APR 1 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Mayfield-Smith Drilling, Inc.  
Address 227 Union Center Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Edgar E. Smith

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Edgar E. Smith  
227 Union Center Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1962

10-26-65

Marguerite Mayfield Notary Public.



**MAYFIELD-SMITH DRILLING, INC.**  
227 Union Center Bldg.  
Wichita, Kansas

#1 METZ NW SE NE  
Sec. 24-11S-19W  
Ellis County, Kansas

Elevation: 2031 Kelly Bushing

Casing: Set 201' of 8 5/8" W/135 Sx. Cement

0 - 110	Lime, Shale & Sand
110 - 517	Blue Shale
517 - 1020	Sand, Shale Streaks
1020 - 1155	Shale
1155 - 1360	Red Bed & Shale
1360 - 1395	Anhydrite
1395 - 1890	Shale & Shells
1890 - 1960	Shale & Lime
1960 - 2020	Shale & Shells
2020 - 3412	Lime & Shale
3412 - 3550	Lime
3550 - 3640	Lime & Conglomerate
3640 - 3652	Arbuckle

Anhydrite	1370	+ 661
Heebner	3262	- 1231
Lansing	3304	- 1273
Arbuckle	3640	- 1609
Total Depth	3652	- 1621

RECEIVED  
STATE CORPORATION COMMISSION  
4-10-1962  
APR 10 1962

CONSERVATION DIVISION  
Wichita, Kansas

[illegible]

I, Edgar E. Smith, do hereby certify that the above and foregoing is a true and correct Log of the #1 Metz, located in the NW SE NE of Section 24, Township 11 South, Range 19 West, Ellis County, Kansas, as reflected by the Daily Drilling Reports of Mayfield-Smith Drilling, Inc.

Edgar E. Smith

State of Kansas )  
\_\_\_\_\_) SS  
County of Sedgwick )

Subscribed and sworn to before me, a Notary Public, in  
and for Sedgwick County, Kansas, this 6th day of April, 1962.

*Marguerite Mayfield*  
Marguerite Mayfield, Notary Public

My Commission Expires:  
10-26-65