

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-24881-00-00

API NUMBER 15-051-24,881

LEASE NAME Solomon

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

990 Ft. from <sup>N</sup> Section Line

2,150 Ft. from <sup>W</sup> Section Line

SEC. 29 TWP. 11 RGE. 19 (X) or (W)

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

COUNTY Ellis

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed 11-6-94

Character of Well D & A

Plugging Commenced 11-6-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-7-94

The plugging proposal was approved on 11-6-94 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3,706'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

| Formation | Content | From | To | Size   | Put in | Pulled out      |
|-----------|---------|------|----|--------|--------|-----------------|
|           |         |      |    | 8 5/8" | 264'   | Cmtd. w/165 sax |
|           |         |      |    |        |        |                 |
|           |         |      |    |        |        |                 |
|           |         |      |    |        |        |                 |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 1,470', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 770', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 300', spot 40 sax on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or ~~Notary Public~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 94

RECEIVED STATE CORPORATION COMMISSION NOV 29 1994 Ruth Phillips Notary Public

My Commission Expires

NOTARY PUBLIC RUTH PHILLIPS State of Kansas My Appt. Exp. 12-16-94 DIVISION



Shields


Russell, Kansas

WELL LOG

15-051-24881-00-00

Operator: Shields Oil Producers, Inc.  
 Well: Solomon #1  
 Commenced: October 31, 1994  
 Completed: November 7, 1994  
 Contractor: Shields Drilling Co.

Well Description: SE NE NW  
 Sec. 29-11S-19W  
 Ellis County, KS.



ORIGINAL

| CASING RECORD |      |                 |
|---------------|------|-----------------|
| Size          | Run  | Pulled          |
| 8 5/8"        | 264' | Cmtd. w/165 sax |

Elevation: 2,119' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

|                    |        |     |
|--------------------|--------|-----|
| Sand & rock        | 10'    |     |
| Rock, sand & shale | 267'   |     |
| Shale & sand       | 1,463' |     |
| Anhydrite          | 1,503' |     |
| Shale & sand       | 1,920' |     |
| Shale & lime       | 3,240' |     |
| Lime               | 3,706' | RTD |

Notes

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-29-1994  
 NOV 29 1994  
 CONSERVATION DIVISION  
 WASHINGTON, MISSOURI