

TQ:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20931-00-00<sup>1</sup>  
Spot: CNESESE Sec/Twnshp/Rge: 27-9S-25W  
1040 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: SPIES A Well Number: 1  
County: GRAHAM Total Vertical Depth: 2222 feet <sup>4118 27 KCC</sup>

Operator License No.: 9067  
Operator Name: DAMAR RESOURCES, INC.  
Address: PO BOX 70  
HAYS, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 304  
Production: Size 5.5 feet: 2222  
Liner: Size \_\_\_\_\_ feet: 72, 22

Well Type: SWD UIC Docket No: D19136.0 Date/Time to Plug: 9/5/00  
Plug Co. License No.: 9067 Plug Co. Name: DAMAR RESOURCES, INC.  
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Order 150 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/05/2000 9:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:  
8 5/8" set at 314' w/230 sxs cwc. 5 1/2" @ 2222' w/425 sxs cwc.  
Perfs @ 1776' - 1952'.  
Squeezed 5 1/2" w/140 sxs cement blend w/500# hulls mixed into  
Max. P.S.I. 800#. Held. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
9-25-00  
SEP 25 2000

Remarks: \_\_\_\_\_ CONSERVATION DIVISION  
Plugged through: \_\_\_\_\_ Wichita, Kansas

District: 04 Signed Carl Goodrow  
KCC (TECHNICIAN)

SEP 18 2000  
HAYS, KS

INVOICED  
DATE 9/26/00  
INV. NO. 2001060749

THE MAURICE L. BROWN CO.  
1500 VICKERS-KSB&T BLDG.

#1 SPIES "A"

27-9-25W  
NE SE SE

WICHITA, KS.

CONTR ABERCROMBIE DRG., INC. CTY GRAHAM

GEOL \_\_\_\_\_ FIELD EMOR NE EXT (1/4 W)

2554 KB CM 7/11/77 CARD ISSUED 8/18/77 IP SWDW  
1776-1952 OA

+	+
+	+

API 15-065-20,931

LOG	TOPS	DEPTH	DATUM
SC	2197	+ 357	
HEEB	3820	-1266	
TOR	3842	-1288	
LANS	3856	-1302	
BKC	4089	-1535	
TD	4118	-1564	
PBTD	2188	+ 366	

8-5/8" 304/230sx, 5 1/2" 2221/425sx  
 DST (1) 3975-4003/30-30-30-60, 15'M,  
 SIP 420-730# FP 37-37# 37-37#  
 DST (2) 4019-43/MIS-RUN, PKR FAILURE  
 DST (3) 3998-4043/30-30-30-60, 15'M,  
 SIP 91-73# FP 55-55# 46-46#  
 DST (4) 4039-67/MIS-RUN, PKR FAILURE  
 DST (5) 4027-67/MIS-RUN, PKR FAILURE  
 DST (6) 4025-4118/45-60-45-60, 25'M,  
 SIP 183-141# FP 91-91# 91-91#  
 MICT - PBTD 2188', PF 1776-8S, 1812-  
 60, 1883-86, 1918-52, SWDW

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS