

6 070936

8-3

204 P

API NUMBER 15- 051-24,754-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SE , SEC. 28 , T 11 S, R 18 WE
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3007

Lease Name Fisher Well # 1

Operator: Western Kansas Exploration

County Ellis 116.02

Name & Address P.O. Box 126

Well Total Depth 3570 feet

Hays, Kansas 67601

Conductor Pipe: Size 0 feet 0

Stan Younger

Surface Casing: Size 8 5/8 feet 210'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083

Address P.O. Box 126, Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 3rd Month: August Year: 19 91

Plugging proposal received from Jim Manley

(company name) Western Kansas Drilling (phone) 913-628-2296

were: 8 5/8" 210' S.P. cir. w/135 sx. 60/40 poz. 2% gel. 3% Ca.Cl. By Halliburton

Elv. 2094' - Arbuckle 3620' - Anhy. 1379' - Mud condition 42 vis. - 9.6 wt. 12.0 wt.

No circulation problems. Proposal 215 sx. 60/40 poz. - 6% gel. - 3% c.c. and 1 sk.

flocele. Circulate hole. Spot with drill stem, heavy mud between all plugs.

25. sx. @ 3570' - 25 sx. @ 1390' - 100 sx. w/1 sx. F.C. @ 794' - 40 sx. @ 260' -

10 sx. @ 40' & 15 sx. in Plugging Proposal Received by Marion J. Schmidt
Rathole (circulate) (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 P.M. Day: 3rd Month: August Year: 19 91

ACTUAL PLUGGING REPORT Western Kansas Drilling ordered 215 sx. 60/40 poz. 6% gel -

3% c.c. and 1 sx. flocele. Circulated hole. Spotted cement through drill stem, heavy mud between all plugs.

1st plug @ 3570' w/25 sx. cement 4th plug @ 260' w/40 sx. cement

2nd plug @ 1390' w/25 sx. cement 5th plug @ 40' x/10 sx. cement

3rd plug @ 794' w/100 sx. cement w/1 sx. F.C. , 15 sx. Rathole (circulate)

Remarks: Cemented by Halliburton Services. (If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
8-21-1991
AUG 21 1991

INVOICED

XXXXXX (do not) observe this plugging.

John S.

Signed Marion J. Schmidt (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

DATE SEP 06 1991

32992