

4-060883

15-051-19071-0000

5-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 12-10-62

SW NE NE /4 SEC. 04 , 11 S, 18 W
4290 feet from S section line
990 feet from E section line

Operator license# 3194

Lease: Warner "D" Well # 2

Operator: Tri-United, Inc.

County: Ellis

Address: 950 270th Avenue
Hays, Kansas 67601

Well total depth 3520 114.40 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 256 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Co Tools License# _____

Address: _____

Company to plug at: Hour: 2:00 P.M. Day: 23 Month: May Year: 1996

Plugging proposal received from: Eugene Leiker

Company: Tri-United, Inc. Phone: 913-628-3670

Were: Order 250 sxs 60/40 posmix - 10% gel and hulls.
Plug with tubing. Operator encountered metal debris dropped into wellbore by unknown parties. Operator fished and recovered much of debris and drove remainder downhole to below base of Cedar Hill sand. Debris lodged in area of bad casing as evidenced by heavy drilling mud in hole.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 4:00 P.M. , Day: 23 , Month: May , Year: 1996

Actual plugging report: 8 5/8" to 256' w/175 sxs. 4 1/2" to 3514' w/150 sxs. Perfs. 3344' - 3346' - 3358' - 3362'. CIBP 3450'. Ran tubing to 1020'. Mixed and pumped cement with cement to surface with 130 sxs. Pulled tubing and tied onto annulus and pumped 10 sxs. Pressured up to 500# and S.I.P. 500#. Apparent prior squeeze. Tied onto production casing and pumped 80 sxs cement with 50# hulls. Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
KANSAS CORPORATION COMMISSION

5-30-1996
MAY 30 1996


Remarks: Allied Cementing.

Condition of casing(in hole): GOOD _____ BAD Anhy.plug: YES NO _____

Bottom plug(in place): YES _____, CALC , NO _____ Dakota plug: YES , NO _____

Plugged through TUBING , CASING _____ . Elevation: 1941

I did did not [] observe the plugging.


DH (agent)
Form CP-2/3

INVOICED
DATE JUN 12 1996
INV. NO. 45781
5-23