

15-051-23558-00-00

R

To: 6 070889
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-23,558
SE , SEC. 34 , T 11 S, R 18 W/E
2310 feet from S section line
1100 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # State Corp Commission
Operator: Conservation Division
Name & Address: Wichita, Ks. 67202
Former operator, Frank Kennec

Lease Name Walters Well # 1
County Ellis
Well Total Depth 3798 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services Paul's Well Service License Number

Address Hays, Ks. Ellis, Ks.

Company to plug at: Hour: AM Day: 17 Month: Nov Year: 19 90

Plugging proposal received from Marion J. Schmidt Don Butcher

(company name) Ks. Corp Comm District #4 (phone)

were: 8 5/8 240 ft. s.p. cwc w/u.k. 5 1/2 casing set at 3724 ft. w/ u.k.

Perfs u.k. Proposal 350 sks 65/35 poz 6% gel and 5 sks hulls.

Perf. 5 1/2 casing at 1295 ft. and 600 ft. Pump in with pump truck. Spot and displace cement through tubing, load both 5 1/2 casing and 5 1/2 x 8 5/8 annulus with cement shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 PM Day: 17 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Ordered 350 sks 65/35 poz 6% gel and 5 sks hulls.

Perf. at 1295 and 600. Pumped in with pump truck, spotted cement through tubing.

1. 2 3/8 tubing at 2000 ft. Spotted w/225 sks cement and 5 sks hulls. Cement circ.
2. Sq annulus with 75 sks cement. Max pressure 300 psig. Shut in at 200 psig.
3. Sq 5 1/2 casing w/50 sks cement. Max pressure 500 psig. Shut in at 150 psig.

Remarks: Cemented by Halliburton Cement.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

J.S.

Signed Marion J. Schmidt (TECHNICIAN)

DEC 16 1990
12-16-1990