

4-110069

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-25,010-0000

NW SE SW /4 SEC. 28, 11 S, 18 W  
990 feet from S section line  
~~3630~~ 1650 feet from W section line

Operator license# 31521

Lease: Fisher Well # 3

Operator: Kenmark Corporation

County: Ellis 116.84

Address: P.O. Box 572  
Hays, Kansas 67601

Well total depth 3595 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling Company, Inc. License# 31548

Address: P.O. Box 763 - Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 12 Month: October Year: 1999

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Company Phone: 785-623-2920

Were: According to KCC Rules and Regulations.

INVOICED

DATE 10-29

PRY# 60785

RECEIVED  
KANSAS CORP COMM  
1999 OCT 27 12 37  
10-27-1999

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 12:01 A.M., Day: 12, Month: October, Year: 1999

Actual plugging report: 8 5/8" set at 221' w/150 sxs 60/40 pozmix - 3% c.c. & 2% gel.

1st Plug at 3550' w/25 sxs - Arbuckle.

2nd Plug at 1340' w/25 sxs - Anhydrite at 1325' - 1358'.

3rd Plug at 730' w/100 sxs - Dakota at 428' - 728'.

4th Plug at 270' w/40 sxs - Surface Pipe 221'.

5th Plug at 40' w/10 sxs and 8 5/8" wiper plug.

15 sxs in rathole.

10 sxs in mousehole.

225 total sxs 60/40 pozmix with 1/4# flocele per sack.

Remarks: Allied Cementing

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2020 GL

I did [ ] / did not [ X ] observe the plugging.

Roger Moses  
(agent)

Form CP-273

(P)