

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 63
SW, Sec. 28, T 9 S, R 25 W/E
330 feet from N/S section line
1000 feet from W/E section line
Lease Name Bolling Well # 4
County Graham
Well Total Depth 2200 feet \$71.50
Conductor Pipe: Size _____ feet _____
Surface Casing: Size 8 5/8 feet 200

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040
Operator: Bankoff oil Co.
Name &
Address Box 3446
Tulsa, Oklahoma

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated SW Supply well
Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 14 Month: 4 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Eldon Reed
(company name) Bankoff oil Co. (phone) 316-564-3587

were: Run tubing to bottom of well
bore down 4 1/2" casing and circulate cement
from bottom to surface.

Con > 50/50 ppg 6 7/8 x 3 9/16 CC Signed Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:40 PM Day: 14 Month: 4 Year: 19 83

ACTUAL PLUGGING REPORT Pumped Cement mix down
2" tubing and Circulated to surface
pulled 2" tubing and loaded hole with
Cement mix. used 200 sp of 50/50 ppg 6 7/8 x 3 9/16 CC

Remarks: 4 1/2" casing was eaten full of holes
and had been circulated on back side to
1000' but not to surface with 500 sp of Cement.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED STATE CORPORATION COMMISSION
4-25-83
DATE 5-3-83 APR 25 1983
INV. NO. 4137-W CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)