

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20749-00-08  
Spot: SESENWSW Sec/Twnshp/Rge: 34-9S-25W  
1420 feet from S Section Line, 4060 feet from E Section Line  
Lease/Unit Name: PETER ROME ESTATE Well Number: 5 W  
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 5030  
Operator Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 1426  
Production: Size 5.5 feet: 4050  
Liner: Size \_\_\_\_\_ feet:

131.63

Well Type: EOR UIC Docket No: E-25314.1 Date/Time to Plug: 9/18/00

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: JOEL 9/18 Company: VESS OIL CORPORATION Phone: \_\_\_\_\_

Proposed Plugging Method: Order 400 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Work string.

Plugging Proposal Received By: CARL GOODROW  
Date/Time Plugging Completed: 09/18/2000 12:14 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 1426' w/500 sxs cwc. 5 1/2" set at 4050' w/200 sxs.  
Prod perfs 3778' - 3787'; 3796' - 4004'. Casing bad from 1736' - 2808'. Ran work string to 3560'. Displaced in stages 320 sxs cement blend w/500# hulls mixed in to surface - hole full.  
Squeezed 8 5/8" w/40 sxs cement blend to Max. P.S.I. 500#.  
Plug complete.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through:

District: 04

Signed Carl Goodrow PERT II  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

10-3-00  
OCT 3 2000

CONSERVATION DIVISION  
Wichita, Kansas

SEP 20 2000

INVOICED  
DATE 10/4/00  
INV. NO. 2001060788

