

1-4 15-065-01641-0000 65

6 031476

API NUMBER 15- _____ 1960

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C. SW SE, SEC. 34, T 9 S, R 25 W/Ex
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name J. Kuhn Well # 4

Operator: Texaco Inc.
Name & Address: Star Route Box 2
Russell, Ks. 67665

County Graham 130.29
Well Total Depth 4009 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor S. O. S. Jet Well Servicing License Number 822

Address Russell, Ks.

Company to plug at: Hour: _____ AM Day: 4 Month: Jan Year: 19 91

Plugging proposal received from John Goosetree

(company name) Texaco Inc. (phone) _____

were: 8 5/8 set at 345 w/210 sks cwc. 4 1/2 set 5 at 400 w/100 sks. PBDT 2379.

Original perf 3938 - 3985. OH 4001 - 4009 Sand back to 2419 w/CIBP at 2379.

Order work string and 400 sks 65/35 poz 8% gel 500 lbs. hulls. B. J. Services.

John Keith Wellbrock Water Trucks. Anhy 2160 - 2200. Sq from 1801 sto 2104.

Fill up to 1643. Holes in casing above 1601. Shot 4 holes at 1300.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 4 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Ran tubing to 1601. Circulated cement blend to surface w/total of 275 sks w/hulls Lightly strung through cement blend., To max psi 350 lbs.

Close in psi 350 lbs. Sq 8 5/8 w/125 sks. To max psi 300 lbs.

Close in psi 200 lbs.

Remarks: _____

INVOICED

DATE FEB 14 1991

INV. NO. 30739

1-4

(If additional description is necessary, use BACK of this form.)

Handwritten initials

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow