

10-7-87 15-065-01638-0000

6 030975

API NUMBER 15- 1960

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C. SE. NE, SEC. 34, T. 9 S, R. 25 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name J. Dreiling Well # 2

Operator: Texaco USA

County Graham 131.98

Name & Address Box 2420

Well Total Depth 4061 feet

Tulsa, Ok 74102

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Plainville, Kansas

Company to plug at: Hour: AM Day: 7 Month: Oct. Year: 19 87

Plugging proposal received from Roy

(company name) Texaco USA (phone)

were: 8 5/8" set at 317' w/250 sks 4 1/2" set at 4050' w/100 sks. Perfs at  
3833' - 4034'. Area between 2173' - 2204' Block squeezed w/125 sks and  
1375' - 1405' w/90 sks. Order 250 sks cement blend, ATL 65/35 Poz 10% Gel  
2% Dical 6 sks Hulls. Allied Cement Co. Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:00AM Day: 7 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/400# Hulls in with 150 sks Cement Blend.

To Max Psi 800# Close in Psi 600#. Squeeze 8 5/8" - 4 1/2" annulus w/2 sks Hulls  
in with 100 sks Cement Blend. To Max Psi 200#. Close in Psi 100#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
12-7-87  
DEC 7 1987

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (did not) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 12-8-87

INV. NO. 19219 10-7 JAN 14 1988