

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20792-00-00
Spot: CNESW Sec/Twnshp/Rge: 35-9S-25W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: VERONICA Well Number: 5
County: GRAHAM Total Vertical Depth: 4073 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 303 150 SX CMT
Production: Size 4.5 feet: 4073 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/27/2002 1:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 260 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/27/2002 6:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 303' w/150 sxs cement. 4 1/2" casing at 4073' w/150 sxs cement.
Squeezed at 1933' w/200 sxs - 2102' w/300 sxs - 2441' w/50 sxs.
Ran tubing to 2520' and circulated with 120 sxs cement and 300# hulls.
Pulled all tubing and squeezed with 90 sxs cement and 300# hulls.
Max. P.S.I. 600#. S.I.P. 400#.
Tied to 8 5/8" annulus and squeezed 50 sxs to Max. P.S.I. 100#. S.I.P.0#.
Total of 260 sxs 60/40 pozmix - 10% gel and 600# hulls.

RECEIVED
7-8-02
JUL 08 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. BALCKHAWK TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger D. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 7-8-02

WV. NO. 2003060006

JUL 01 2002

KIMBARK OPERATING CO. #B VERONICA 35-0-25W
 REC. LINCOLN ST., DENVER, CO. C NE SA
 CONTR. HELBERG DRLG. CO. CITY GRAHAM

GEOL. _____ FIELD EMOR

E 2539 VE CH 2/2/76 CARD ISSUED 4/15/76 IP P 25 EOPD N/W
 LKC 3990-96

API 15-085-20,792

LOG	TOPS	DEPTH	DATUM
SC		2170	+ 369
B SC		2212	+ 327
TOP		3767	-122R
HEFB		3789	-123J
TOP		3817	-127B
LKC		3828	-1289
RTD		4073	-1534

E 5/8" 303/150sx, 4 1/2" 4073/150sx
 DST (1) 3813-75/30-30-45-30, 10' M, SIP
 521-447#, FP 45-49#
 DST (2) 3938-4000/30-30-45-30, 150' GIP,
 90' OIL SP M, SIP 235-398#, FP 49-
 62#
 MICT - PF 3915-17, 3990-96, A 3500, SQZ
 3915-17, REC LD, PO

INDEPENDENT OIL & GAS SERVICE