

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20760-00-00²
Spot: C/NENWSW Sec/Twnshp/Rge: 35-9S-25W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: VERONICA Well Number: 4
County: GRAHAM Total Vertical Depth: 4060 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size _____ feet: 131.95
Surface Casing: Size 8.625 feet: 219 225 SX CMT
Production: Size 4.5 feet: 4059 250 SX CMT
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2002 11:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 350 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/26/2002 4:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 219' w/225 sxs cement. 4 1/2" casing at 4059' w/250 sxs cement.
D.V. at 2146' w/400 sxs cement.
Ran tubing to 2734' - pumped 100 sxs cement and 300# hulls.
Pulled tubing to 1350' - circulated with 160 sxs cement and 300# hulls.
Pulled all tubing and topped off with 40 sxs cement.
Tied to 8 5/8" x 4 1/2" - squeezed 50 sxs cement to Max. P.S.I. 100#.
Total of 350 sxs 60/40 pozmix - 10% gel - 600# hulls.

RECEIVED
7-8-02
JUL 08 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. BLACKHAWK TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 7-8-02

INV. NO. 2002060006

JUL 01 2002

KIMBARK OPERATING CO. #4 VERONICA
 1860 LINCOLN ST., DENVER, COLO.
 CONTR. HELBERG DRLG. CO. CITY GRAHAM

35-9-25W
 NE NW SW

GEOL. J.R. GREEN FIELD EMOR

2519 KB CM 6/18/75 ^{CARD} 8/7/75 IP P 44 BOPD 4 BWPD +
 16 MCFGPD/LANS 3834-4006
 API 15-065-20,760

LOG TOPS	DEPTH	DATUM
TOP	3545	-1026
HEEB	3764	-1245
TOR	3787	-1268
LKC	3803	-1284
BKC	4033	-1514
RTD	4060	-1541
SC-Tip	2150	
SI-Base	2192	

S 5/8" 219/225SX, 4 1/2" 4059/250SX
 NO DST'S
 MICT - PF 3960-63, 3936-41, 4002-06,
 3846-50, 3834-38, AC 4000, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS