

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20240-00-01²
Spot: CSWNENW Sec/Twnshp/Rge: 7-9S-26W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: HAFFNER Well Number: 3
County: SHERIDAN Total Vertical Depth: 3990 feet
4050 RT KCC

Operator License No.: 4661 Conductor Pipe: Size _____ feet:
Op Name: GALLOWAY PETROLEUM EXPLORATIO Surface Casing: Size 8.625 feet: 287 w/175 sxs cmt
Address: 105 S. BROADWAY, #360 Production: Size 4.5 feet: 4049 w/125 sxs cmt 129.68
WICHITA, KS 67202 Liner: Size _____ feet:

Well Type: EOR UIC Docket No: E23131.1 Date/Time to Plug: 03/09/2001 8:00 AM
Plug Co. License No.: 31668 Plug Co. Name: H & H INVESTMENTS
Proposal Rcvd. from: RON Company: H & H INVESTMENTS Phone: (785) 625-6636

Proposed Order 10 yards Redi-Mix.
Plugging Well abandon by Galloway Petroleum - no T-1 available.
Method: This project completed through an agreement between the land and lease owner, Phil Heier, and the contractor, H&H Investments, to plug out and clean up the lease for salvage.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/09/2001 9:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 287' w/175 sxs cwc.
4 1/2" set at 4049' w/125 sxs.
Perf at 1355' -w/385 sxs to Max. P.S.I. 1000#.
Perf at 650' w/200 sxs to Max. P.S.I. 500#.
Prod. Perf. 3942' - 3948'.
8 5/8" casing - took about one yard Redi-Mix.
Filled 4 1/2" to surface with 9 yards Redi-Mix.
Fluid Level at 1950'.
Plug complete.

INVOICE
DATE 3-30-01
WEL NO. 2001061554

RECEIVED
STATE CORPORATION COMMISSION
3-29-01
MAR 29 2001

Remarks:

Plugged through: CSG


District: 04

Signed Carl Goodrow
(TECHNICIAN)

MAR 19 2001

RAINS & WILLIAMSON OILCO.
 435 PAGE COURT 220 W. DOUGLAS #3 HAFFNER 'OWWO' 7-9-26W
 WICHITA, KS. 67202 SW NE NW
 CONTR RAINS & WILLIAMSON OIL CTY SHERIDAN

GEOL _____ FIELD GEORGE NW
 E 2610 KB CM 3/15/79 CARD ISSUED 8/11/79 IP P 35 BOPD
 LANS 3942-48



API 15-179-20,240-A

LOG	TOPS	DEPTH	DATUM
ANH		2208	+ 402
HEEB		3716	-1106
TOR		3736	-1126
LANS		3756	-1146
BKC		3979	-1369
LTD		3993	-1383
RTD		3990	-1380
DDTD		4050	-1440

OLD INFO: OPERATOR WAS BEACON RESOURCES.
 #1 HAFFNER ET AL SPD 12/4/69 SET 8-5/8"
 287/175 SX COMPLETED AS D&A/BKC 12/31/
 69.
 DST (1) 3810-34 (LANS) 70", 590' MW SIP
 1306-1275#/30", FP 83-270#
 DST (2) 3865-92 (LANS) 70", 50' M FEW
 SP 0, SIP 1327-1192#/30", FP 41-41#
 DST (3) 3910-33 (LKC) 70", 15' M SIP 62-
 31#/30", FP 31-31#

NO CORES

RE-ENTERED 3/15/79 WSH DWN DDTD 4050'
 4 1/2" 4049/125SX MICT - CO, PF (LANS)
 3942-48, AC 250 GAL, SWB TST 6 BO/3HRS,
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS