

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20505-00-00
Spot: CNWNWNE Sec/Twnshp/Rge: 7-9S-26W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: HAFFNER A Well Number: 1
County: SHERIDAN Total Vertical Depth: 4030 feet

Operator License No.: 31668
Op Name: H & H INVESTMENTS
Address: PO BOX 1433
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 363 w/250 sxs
Production: Size 4.5 feet: 4029 w/150 sxs 390.98
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/09/2001 12:00 PM
Plug Co. License No.: 31668 Plug Co. Name: H & H INVESTMENTS
Proposal Rcvd. from: RON Company: H & H INVESTMENTS Phone: (785) 625-6636

Proposed Plugging Method: Order 10 yards Redi-Mix.
This project completed through an agreement between the land and lease owner, Phil Heier, and the contractor H&H Investments, to plug out and clean up the lease for salvage.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/09/2001 2:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 363' w/250 sxs cwc.
4 1/2" set at 4029' w/150 sxs.
Prod. Perfs 3967' - 3974'. Fluid Level at 2000'.
Filled 8 5/8" to surface with 2 yards Redi-Mix.
Filled 4 1/2" to surface with 8 yards Redi-Mix.
Casing tight - could not pull. Heavy mud behind the 4 1/2".
Plug complete.

INVOICED
DATE 3-30-01
WV. NO. 2001061553

RECEIVED
STATE CORPORATION COMMISSION
3-29-01

MAR 29 2001

Remarks:

Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

MD

so

Form CP-2/3

MAR 15 2001

RAINS & WILLIAMSON OIL CO., INC.
435 PAGE COURT, 220 W. DOUGLAS

7-9-26W
NW NW NE

WICHITA, KS.
CONTR CO. TOOLS

CTY SHERIDAN

GEOL NEIL SIKES

FIELD GEORGE NW EXT (1/8 E)

E 2638 KB CM 4/27/78 CARD ISSUED 6/29/78 IP P 120 BOPD, NW
LANS 3967-74

+	+	+
+	+	+
+	+	+

API 15-179-20,505

LOG	TOPS	DEPTH	DATUM
ANH		2235	+ 403
HEEB		3743	-1105
TOR		3764	-1126
LANS		3780	-1142
BKC		4002	-1364
LTD		4028	-1390
RTD		4030	-1392

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

8-5/8" 363/250sx, 4 1/2" 4029/150sx
DST (1) 3751-95/30-30-60-60, 84' MSW
300' SW, SIP 1200-1190#, FP 21-83#
93-165#, BHT 112°
DST (2) 3797-3823/30-30-60-60, 5' CL
OIL, 20' MSW, 560' SW, SIP 1055-
1055#, FP 21-134#, 145-362#, BHT
110°
DST (3) 3840-63/30-30-60-60, 10' OIL,
50' OCM, 60' MSW, 340' SW, SIP 1221-
1200#, FP 21-114#, 114-217#
DST (4) 3937-60/30-30-60-60, 285' OIL,
45' OIL, 45' OCM, SIP 1076-1055#
FP 21-21#, 21-41#
DST (5) 3956-80/30-30-60-60, 1140' GIP
(OVER)