

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20496-00-00  
Spot: CN2NENW Sec/Twnshp/Rge: 7-9S-26W  
4950 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: HAFFNER Well Number: 2  
County: SHERIDAN Total Vertical Depth: 3980 feet

Operator License No.: 31668  
Op Name: H & H INVESTMENTS  
Address: PO BOX 1433  
HAYS, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 314 w/250 sxs  
Production: Size 4.5 feet: 3979 w/150 sxs  
Liner: Size \_\_\_\_\_ feet:

390.08

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2001 3:00 PM  
Plug Co. License No.: 31668 Plug Co. Name: H & H INVESTMENTS  
Proposal Rcvd. from: RON Company: H & H INVESTMENTS Phone: (785) 625-6636

Proposed Order 10 yards Redi-Mix.  
Plugging This project completed through an agreement between the land and lease owner, Phil Heier, and the contractor, H&H  
Method: Investments, to plug out and clean up the lease for salvage.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/09/2001 4:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 314' w/250 sxs cwc.  
4 1/2" set at 3979' w/150 sxs.  
Prod. Perfs 3919' - 3926'.  
Filled 8 5/8" with 2 yards Redi-Mix.  
Filled 4 1/2" with 8 yards Redi-Mix.  
Could not recover enough 4 1/2" casing to pull.  
Fluid Level at 2200'.  
Heavy mud behind the 4 1/2".  
Plug complete.

INVOICED  
DATE 3-30-01  
INV. NO. 2001061553

RECEIVED  
STATE CORPORATION COMMISSION  
3-29-01

MAR 29 2001

Remarks:  
Plugged through: CSG

CONSERVATION DIVISION  
Wichita, Kansas

District: 04

10

Signed Carl Goodrow  
(TECHNICIAN)

MAR 15 2001

JO

RAINS & WILLIAMSON OIL CO., INC. 7-9-26W  
 435 PAGE COURT, 220 W. DOUGLAS #2 HAFFNER N/2 NE NW  
 WICHITA, KS.  
 CONTR CO. TOOLS \_\_\_\_\_ CTY SHERIDAN  
 GEOL NEAL SIKES \_\_\_\_\_ FIELD GEORGE NW CONF  
 E 2598 KB CM 1/30/78 CAKD ISSUED 3/30/78 IF P 92 BOPD  
 LANS 3919-26

+	+
+	+
+	+

API 15-179-20,496

LOG	TOPS	DEPTH	DATUM
*ANH		2193	+ 405
*B ANH		2227	+ 371
HEEB		3698	-1100
TOR		3717	-1119
LANS		3735	-1137
BKC		3955	-1357
LTD		3980	-1382
RTD		3980	-1382
*SMP TOPS			

8-5/8" 314/250sx, 4 1/2" 3979/150sx  
 DST (1) 3698-3754/30-30-60, 2420' GIP,  
 1130' MSW, ISIP 1213#, NO FSIP, FP  
 42-538#  
 DST (2) 3755-3820/30-30-60-60, 925'  
 MSW W/F SPKS OIL, SIP 1203-1213#  
 FP 74-401#  
 DST (3) 3842-76/30-30-60-60, 880' GIP  
 260' CL OIL, 130' HOOGM (53% GSY  
 OIL, 47% M) (GR 40°), SIP 1297-  
 1287#, FP 42-169#  
 DST (4) 3880-95/30-30-30-30, 1'M, ALL  
 PRESS 11#  
 DST (5) 3892-3910/30-30-60-60, 100'  
 GIP, 40' CO, 160' OCM, SIP 1034-1297#  
 FP 42-105# (OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS