

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20449-00-00
Spot: CNENWNW Sec/Twnshp/Rge: 7-9S-26W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: HAFFNER Well Number: 1
County: SHERIDAN Total Vertical Depth: 4020 feet

Operator License No.: 31668
Op Name: H & H INVESTMENTS
Address: PO BOX 1433
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 333 w/225 sxs
Production: Size 4.5 feet: 4019 w/125 sxs 390.98
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/09/2001 11:00 AM
Plug Co. License No.: 31668 Plug Co. Name: H & H INVESTMENTS
Proposal Rcvd. from: RON Company: H & H INVESTMENTS Phone: (785) 625-6636

Proposed Order 10 yards Redi-Mix.
Plugging This project completed through an agreement between the land and lease owner, Phil Heier, and the contractor, H&H
Method: Investments, to plug out and clean up the lease for salvage.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/09/2001 12:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 333 w/225 sxs cwc.
4 1/2" set at 4019' w/125 sxs.
Prod Perfs 3952' - 3958'.
Filled 8 5/8" to surface with 2 yards of Redi-Mix.
Filled 4 1/2" to surface with 8 yards of Redi-Mix.
Fluid Level at 1950'.
Casing tight - could not pull - heavy mud behind the 4 1/2".
Plug complete.

INVOICED
DATE 3-30-01
WV. NO. 2001061553

RECEIVED
STATE CORPORATION COMMISSION
3-29-01
MAR 29 2001

Remarks:

Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas

District: 04

Signed Carl Goodrow
(TECHNICIAN)

Form CP-2/3

MAR 15 2001

RAINS & WILLIAMSON OIL CO., INC. #1 HAFFNER 7-9-26W
 435 PAGE COURT, 220 W. DOUGLAS NE NW NW
 WICHITA, KS. CTY SHERIDAN
 CONTR CO. TOOLS FIELD WC (GEORGE. NW DISC)
 GEOL JAY DIRKS
 E 2620 KB CM 4/1/77 CARD ISSUED 12/15/77 IP P 116 BOPD, NW
 LANS 3952-58

.	.	.
+	+	+
+	+	+
+	+	+

API 15-179-20,449

LOG	TOPS	DEPTH	DATUM
ANH		2222	+ 398
HEEB		3724	-1104
TOR		3744	-1124
LANS		3765	-1145
BKC		3986	-1366
LTD		4024	-1404
RTD		4020	-1400

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

8-5/8" 333/225sx, 4 1/2" 4019/125sx
 DST (1) 3719-3820/30-30-60-30, 270' MW
 SIP 1222-1192#, FP 61-112#, 112-173#, BHT 109°
 DST (2) 3866-3905/30-30-60-30, 30' MW
 SIP 1161-1010#, FP 30-40#, BHT 110°
 DST (3) 3914-40/30-30-30-30, 10' M w/
 SPTS 0, SIP 82-30#, FP 20-20#
 DST (4) 3937-60/30-30-60-30, 1' 00" GIP
 1320' FO, 120' SMCO, SIP 1252-1192#
 FP 61-224#, 265-510#
 MICT - SWB DWN 3000', PF 12/3952-58.
 1000' FIH, SWB DWN & DRIED UP, LAST
 PULL ALL OIL, ON/FU 3150' FL, SWB
 DWN 950' OB, SWB 12 BOPH, NW/3 HRS
 R&T, POP