

4-060445

10-3
15-051-24843-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,843

NW NW SW /4 SEC. 19 , 11 S, 19 W
2310 feet from S section line
4950 feet from E section line

Operator license# 6569

Lease Kohl well # 1

Operator: Carmen Schmitt, Inc.

County Ellis

116.48

Address: 3111 10th. Street
P.O. Box 47
Great Bend, Kansas 67530

Well total depth 3584 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 210 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 9:30A.M. Day: 3 Month: October Year: 93

Plugging proposal received from: Lloyd Dellette

Company: Murfin Drilling Company Phone:

Were: Order 215 sxs. 60/40 posmix - 6% gel - 1/4# flocele per. sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:30A.M., Day: 3, Month: October, Year: 93

Actual plugging report:
1st. plug at 3545' w/25 sxs. - Arbuckle at 3555'.
2nd. plug at 1360' w/25 sxs. - Andydrite 1342' - 1385'.
3rd. plug at 625' w/100 sxs. - Dakota 323' - 623'.
4th. plug at 260' w/40 sxs. - Surface pipe 210'.
5th. plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1993
10-18-1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation? 1973 CL

I did did not [X] observe the plugging.

Herb Deines
A/H (agent)

INVOICED
DATE 10-22-93
39023
10-3