

15-051-25138-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25138-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 19-11S-19W
1060 feet from S Section Line, 2290 feet from E Section Line
Lease/Unit Name: GREATHOUSE Well Number: 7
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

Conductor Pipe: Size _____ feet: 8 1/20 25
Surface Casing: Size 8.625 feet: 218
Production: Size _____ feet:
Liner: Size _____ feet:

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/15/2002 12:30 AM

Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC

Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Order 225 sxs 60/40 pozmix- 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 06/15/2002 1:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:
1st. Plug at 3670' w/25 sxs. Arbuckle 3670'.
2nd Plug at 1475' w/25 sxs. Anhydrite 1460' - 1500'.
3rd. Plug at 750' w/100 sxs. Dakota 435' - 735'.
4th. Plug at 270' w/40 sxs. Surface pipe to 218'.
5th. Plug at 40 sxs w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.


RECEIVED
6-21-2002
JUN 21 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed  (TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-24-02

INV. NO. 2002061994

JUN 18 2002