

4-061231

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-25,049-0000

NE SE NE /4 SEC. 19, 11 S, 19 W
3430 feet from S section line
430 feet from E section line

Operator license# 32511

Lease: Marjorie "H" Well # 19-2

Operator: Imperial American Oil Corp.

County: Ellis 117.16

Address: 10004 W. 20th St. N.
Wichita, Kansas 67212

Well total depth 3605 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1325 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 5:00 A.M. Day: 31 Month: July Year: 2000

Plugging proposal received from: Lance Finnesy

Company: Murfin Drilling Phone: -

Were: Order 175 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Penetrated ar buckle but too tight to give up fluids.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 8:00 A.M., Day: 31, Month: July, Year: 2000

Actual plugging report:
1st. Plug at 1375' w/50 sxs cement. Anhydrite 1322' - 1361'.
2nd. Plug at 700' w/100 sxs cement. Dakota 313' - 613'.
3rd. Plug at 40' w/10 sxs cement.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing in hole): GOOD X BAD
Bottom plug(in place): YES___, CALC___, NO X
Plugged through TUBING___, CASING___ Elevation: 1963 GL
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did[] / did not[X] observe the plugging.

INVOICED
DATE 8/3/00
1060296

(agent)
Form CP-2/3
RECEIVED
STATE CORPORATION COMMISSION
8-1-2000
AUG 1 2000
CONSERVATION DIVISION
Wichita, Kansas