



CONFIDENTIAL

15-051-25016-00-00  
SIDE TWO

ORIGINAL

Operator Name Imperial American Oil Corporation Lease Name Vada Belle Unit Well # 18-1

Sec. 18 Twp. 11S Rge. 19W  East County Ellis  West

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken  Yes  No  
(Attach Additional Sheets.)  
Samples Sent to Geological Survey  Yes  No  
Cores Taken  Yes  No  
Electric Log Run  Yes  No  
(Submit Copy.)  
List All E.Logs Run: Compensated Neutron Density; Sonic  
By ELI **DIL**

Name	Formation (Top), Depth and Datums	
	Top	Datum
Anhydrite	1357	+647
Base	1400	+604
Topeka	2998	-994
Heebner Shale	3218	-1214
Toronto	3234	-1230
Lansing	3256	-1252
Base KC	3479	-1475
Marmaton	3496	-1492
Arbuckle	3570	-1553
T.D.	3646	-1642

**KCC**  
**4-25-2000**  
**APR 25 2000**

CONFIDENTIAL

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface Casing (New)	12-1/4"	8-5/8"	24#	1381	60/40 Pozmix	450	3%CaCl, 2% gel
Production (New)	7-7/8"	5-1/2"	14#	3645'	ASC Common	200	10% salt 2% gel
Note: Full returns of cement to surface on Surface Casing Cementing Job.							

ADDITIONAL CEMENTING/SQUEEZE RECORD					
Purpose:	Top	Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
Perforate					
___ Protect Casing					
___ Plug Back TD					
___ Plug Off Zone					

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	3573-3578	None	

RELEASED  
5-7-2001  
MAY 07 2001

TUBING RECORD		Size	Set	None	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
		2-7/8" OD	3574			

DATE OF FIRST, RESUMED PRODUCTION, SWD OR INJ. March 1, 2000

PRODUCING METHOD  Flowing  Pumping  Gas Lift  Other (Explain)

Estimated Production Per 24 Hours	Oil	Bbls.	Gas	Mcf	Water	Bbls.	Gas-Oil Ratio	Gravity
		45	Nil			0	Nil	25

Disposition of Gas: METHOD OF COMPLETION Production Interval 3573-3578  
 Vented  Sold  Used on Lease  Open Hole  Perf.  Dually Comp.  Commingled  
(If vented, submit ACO-18.) No Gas being produced  Other (Specify)

RECEIVED  
CORPORATION COMMISSION  
STATE CORP  
APR 25 2000  
4-25-2000  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
CORPORATION COMMISSION  
STATE CORP  
APR 25 2000  
4-25-2000  
CONSERVATION DIVISION  
Wichita, Kansas

15-051-25016-00-00

# ALLIED CEMENTING CO., INC.

2213

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

**CONFIDENTIAL**

**ORIGINAL**

SERVICE POINT

DATE <u>Z-10-00</u>	SEC. <u>18</u>	TWP. <u>11</u>	RANGE <u>19</u>	CALLED OUT	ON LOCATION <u>8:30 am</u>	JOB START <u>11:15pm</u>	JOB FINISH <u>11:45pm</u>
LEASE <u>Vade Bellemit</u>		WELL # <u>18-1</u>		LOCATION <u>Yocemento &amp; Riverview Rd</u>	COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)				<u>2w 1/2 N</u>			

CONTRACTOR Murfin #8

TYPE OF JOB Production String

HOLE SIZE 7/8 T.D. 3646

CASING SIZE 5 1/2 14" DEPTH 3645

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT 40'

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED 200 ASC 10% salt

290 gal

500 gal WFR-2

DISPLACEMENT 88 bbl

EQUIPMENT \_\_\_\_\_

COMMON	@	_____	_____
POZMIX	@	_____	_____
GEL	@	<u>4</u>	<u>950</u>
CHLORIDE	@	_____	<u>3800</u>
ASC	@	<u>200</u>	<u>164000</u>
SALT	@	<u>18</u>	<u>12600</u>
WFR-2	@	<u>500 gals</u>	<u>50000</u>
HANDLING	@	_____	_____
MILEAGE	@	<u>42/sy/mile</u>	<u>21000</u>

PUMP TRUCK # 153 CEMENTER Mark

BULK TRUCK # 213 DRIVER Jason

BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

KCC	RELEASED	TOTAL	<u>267400</u>
<u>4-25-2000</u>	<u>5-7-2001</u>		
<u>APR 25 2000</u>	<u>MAY 07 2001</u>		

**REMARKS:**

Cent on 135, 11, 1313, 44, 64

Scratchers on 234, 56, 189 3 each

15 sy e Rathole 10 sy e Mousehole

Float Held

Drinks

**CONFIDENTIAL** SERVICE FROM CONFIDENTIAL...

DEPTH OF JOB	_____	_____
PUMP TRUCK CHARGE	_____	<u>108000</u>
EXTRA FOOTAGE	@	_____
MILEAGE	@	<u>20</u> <u>285</u> <u>5700</u>
PLUG <u>5 1/2 Rubber</u>	@	<u>5000</u>
TOTAL		<u>118700</u>

CHARGE TO: Imperial American Oil Co

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**FLOAT EQUIPMENT**

<u>5 1/2</u>	_____	_____
1- insert	@	<u>16000</u>
1- Grade Sive	@	<u>11000</u>
24- Recip Scratchers	@	<u>2750</u> <u>66000</u>
10- Cent	@	<u>2500</u> <u>25000</u>

TOTAL 118000

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Mark Stentor

PRINTED NAME

ALLIED CEMENTING CO., INC.

15-051-25016-00-00

ORIGINAL

P.O. BOX 31  
RUSSELL, KS 67665  
PH (785) 483-3887  
FAX (785) 483-5566

\*\*\*\*\*  
\* I N V O I C E \*  
\*\*\*\*\*

CONFIDENTIAL

Invoice Number: 080662

Invoice Date: 02/10/00

RELEASED  
5-7-2001  
MAY 07 2001

Sold Imperial American Oil Cor  
To: 10004 W. 20th St. N  
Wichita, KS  
67212

KCC  
4-25-2000  
APR 25 2000  
CONFIDENTIAL

FROM CONFIDENTIAL

Cust I.D.: ImpAm  
P.O. Number: VadeBelle 18-1  
P.O. Date: 02/10/00

Due Date: 03/11/00  
Terms: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Gel	4.00	SKS	9.5000	38.00	E
ASC	200.00	SKS	8.2000	1640.00	E
Salt	18.00	SKS	7.0000	126.00	E
WFR-2	500.00	GAL	1.0000	500.00	E
Handling	200.00	SKS	1.0500	210.00	E
Mileage (20) 200 sks @ \$.04 per sk per mi	20.00	MILE	8.0000	160.00	E
Production String	1.00	JOB	1080.0000	1080.00	E
Mileage pmp trk	20.00	MILE	2.8500	57.00	E
Rubber plug	1.00	EACH	50.0000	50.00	E
Insert	1.00	EACH	160.0000	160.00	E
Guide Shoe	1.00	EACH	110.0000	110.00	E
Rec. Scratchers	24.00	EACH	27.5000	660.00	E
Centralizers	10.00	EACH	25.0000	250.00	E

All Prices Are Net, Payable 30 Days Following  
Date of Invoice. 1 1/2% Charged Thereafter.  
If Account CURRENT take Discount of \$ 1008.20  
ONLY if paid within 30 days from Invoice Date

Subtotal: 5041.00  
Tax: 0.00  
Payments: 0.00  
Total: 5041.00

VADA BELLE  
Pd  
2/17/00  
# 589

5 1/2"

1008.20  
4032.80

15-051-25016-00-00

# ALLIED CEMENTING CO., INC. 7854

CONFIDENTIAL

ORIGINAL  
SERVICE POINT: R

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

DATE <u>2-3-00</u>	SEC <u>18</u>	TWP <u>11S</u>	RANGE <u>19W</u>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>10:00 AM</u>
LEASE <u>Vada Belle Unit</u>	WELL # <u>18-1</u>	LOCATION <u>Kocemento T-70 12 N 2W</u>			COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one) <u>NEW</u>				<u>1/4 N</u>			

CONTRACTOR Murfin Drly

TYPE OF JOB Long Surface

HOLE SIZE 12 1/4 T.D. 1381

CASING SIZE 8 1/8 DEPTH 1381

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 20-25'

PERFS.

DISPLACEMENT 24# 86 1/2 BBL

OWNER

CEMENT

AMOUNT ORDERED 450 40 3% CC 2% gel

EQUIPMENT

345

PUMP TRUCK # 345 CEMENTER Dave HELPER Mark

BULK TRUCK # DRIVER

BULK TRUCK # 254 DRIVER Jason

COMMON	<u>270</u>	@ <u>6.35</u>	<u>1714.50</u>
POZMIX	<u>180</u>	@ <u>3.25</u>	<u>585.00</u>
GEL	<u>9</u>	@ <u>9.50</u>	<u>85.50</u>
CHLORIDE	<u>14</u>	@ <u>28.00</u>	<u>392.00</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>450</u>	@ <u>1.05</u>	<u>472.50</u>
MILEAGE	<u>44 per sk per mile</u>		<u>342.00</u>
	<u>19 miles</u>		
	<u>KCC</u>		
	<u>4-25-2000</u>		
	<u>5-7-2001</u>		
			TOTAL <u>3591.50</u>

REMARKS: Cent on 2 & 6

Cement Cir

SERVICE

DEPTH OF JOB

PUMP TRUCK CHARGE 0-300' 580.00

EXTRA FOOTAGE @

MILEAGE 19 @ 2.85 54.15

PLUG 8 1/8 solid Rubber @ 22.50 90.00

@

@

TOTAL 724.15

CHARGE TO: Imperial American Oil Corp

STREET 10004 W 20th St N

CITY Wichita STATE Ks ZIP 67212

FLOAT EQUIPMENT

2 Centralizers 30.00 ea 60.00

@

@

@

@

TOTAL

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX

TOTAL CHARGE

DISCOUNT RELEASED IF PAID IN 30 DAYS

5-7-2001  
MAY 07 2001

PRINTED NAME

FROM CONFIDENTIAL

**ALLIED CEMENTING CO., INC.**

P.O. BOX 31  
 RUSSELL, KS 67665  
 PH (785) 483-3887  
 FAX (785) 483-5566

CONFIDENTIAL

15-051-25016-00-00

ORIGINAL

INVOICE

Invoice Number: 080596

Invoice Date: 02/03/00

Sold Imperial American Oil Cor  
 To: 10004 W. 20th St. N  
 Wichita, KS  
 67212

KCC  
 4-25-2000  
 APR 25 2000

CONFIDENTIAL

Cust I.D.....: ImpAm  
 P.O. Number...: VadaBelle 18-1  
 P.O. Date....: 02/03/00

Due Date.: 03/04/00  
 Terms....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	270.00	SKS	6.3500	1714.50	E
Pozmix	180.00	SKS	3.2500	585.00	E
Gel	9.00	SKS	9.5000	85.50	E
Chloride	14.00	SKS	28.0000	392.00	E
Handling	450.00	SKS	1.0500	472.50	E
Mileage (19)	19.00	MILE	18.0000	342.00	E
450 sks @ \$.04 per sk per mi					
Long Surface	1.00	JOB	580.0000	580.00	E
Mileage pmp trk	19.00	MILE	2.8500	54.15	E
Rubber plug	1.00	EACH	90.0000	90.00	E
Centralizers	2.00	EACH	30.0000	60.00	E

All Prices Are Net, Payable 30 Days Following  
 Date of Invoice. 1 1/2% Charged Thereafter.  
 If Account CURRENT take Discount of \$ 875.13  
 ONLY if paid within 30 days from Invoice Date

Subtotal: 4375.65  
 Tax.....: 0.00  
 Payments: 0.00  
 Total....: 4375.65

- 875.13  
3500.52

RELEASED  
 5-7-2001  
 MAY 07 2001

FROM CONFIDENTIAL