


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 35 Twp. 9 Rge. 25 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Empire Drilling Company
Lease Name Spies Well No. 3
Office Address 650 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 4, 1960 19
Application for plugging filed April 4, 1960 19
Application for plugging approved April 4, 1960 19
Plugging commenced April 4, 1960 19
Plugging completed April 4, 1960 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4095 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	194	8 5/8"	172'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 400' with 20 sacks cement
Plug set at 170' with 20 sacks cement
Plug set at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
4-15-60
APR 15 1960
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650-4th Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 60



Lucille H. Harr
Notary Public.

My commission expires October 21, 1962

15-065-0209-0060

LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Spies # 3
 LOCATION: C NW NW of Section 35-9-25, Graham County, Kansas
 COMMENCED: March 25, 1960
 COMPLETED: April 4, 1960
 ELEVATION: 2554 KB
 POTENTIAL: D & A

0	to	194	Surface
194	to	400	Shale
400	to	2050	Shale-Shells
2050	to	2225	Shale-Anhydrite
2225	to	2555	Shale-Shells
2555	to	2800	Shells-Shale
2800	to	2915	Lime-Shale
2915	to	3015	Shale-Lime
3015	to	3170	Shale-Shells
3170	to	3265	Shale-Lime
3265	to	3320	Lime-Shale
3320	to	3570	Shale-Lime
3570	to	3840	Lime-Shale
3840	to	3915	Lime
3915	to	3955	Lime-Shale
3955	to	4045	Lime
4045	to	4095	Lime-Shale
4095			Rotary Total Depth

SET: 172' 8 5/8" casing with 100 sacks cement.

ELECTRIC LOG TOPS:

Heebner	3812	-1258
Toronto	3833	-1279
Lansing	3843	-1289
Zone 2	3878	-1324
Zone 2A	3890	-1336
Zone 6	3985	-1431
Zone 6A	4006	-1452
Zone 7	4029	-1475
Zone 8	4049	-1495
Base Kansas City	4078	-1524
Schlumberger TD	4095	

RECEIVED
 STATE CORPORATION COMMISSION
 APR 15 1960
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Spies # 3, C NW NW of Section 35-9-25, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

SUBSCRIBED and sworn to before me, a Notary Public within and for Sedgwick County, Kansas, this 14th day of April, 1960.

Lucille H. Harr
 Lucille H. Harr

My commission expires October 21, 1962.

