

15-065-20074-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 35 Twp. 9S Rge. 25W ~~XB~~ (W)  
Location as "NE/CNW/SW" or footage from lines 150' W. C. NE NW  
Lease Owner Bankoff & Leben  
Lease Name Spies Well No. 1  
Office Address Box 486, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-18-67 19  
Application for plugging filed 8-18-67 19  
Application for plugging approved 8-18-67 19  
Plugging commenced 8-18-67 19  
Plugging completed 8-18-67 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4085 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted w/100 sks. cement @ 2000'  
Spotted w/20 sks. cement @ 250, plug, 1/2 sk. hulls,  
@ 40' w/10 sks. cement

RECEIVED  
AUG 23 1967  
KANSAS STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 67

My commission expires April 1, 1971

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY: Bankoff & Leben  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: SPIES #1  
 LOCATION: 150' West of C NE NW  
 SECTION 35-9S-25W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 8-10-67  
 COMPLETED: 8-18-67

0	150	Clay, Sand
150	251	Shale, Shells
251	1280	Shale
1280	1515	Sand, Shale
1515	1940	Sand, Redbed
1940	2060	Shale, Shells
2060	2200	Shale
2200	2230	Anhydrite
2230	2380	Shale
2380	2830	Shale, Lime
2830	2960	Lime, Shale
2960	3155	Shale, Lime
3155	3640	Lime, Shale
3640	3765	Topeka Lime
3765	3956	Lime
3956	4042	Kansas City Lime
4042	4085	Lime
	<u>4085</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CONSERVATION COMMISSION  
 AUG 23 1967  
 CONSERVATION DIVISION  
 Wichita, Kansas


8 5/8" new 17.65# surface casing set @ 251' cemented with 175 sacks  
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is  
 a true and correct copy of the log of the Spies #1 Well, located 150'  
 West of C NE NW of Section 35, Township 9 South, Range 25 West Graham  
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in  
 and for Barton County, Kansas, this 22nd day of August, 1967.



Ulanda Nichols  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1971