

15-051-24804-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-24804-00-00

LEASE NAME G. Herrman

WELL NUMBER 1

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 3 TWP. 11 RGE. 19 (E) or (W)

COUNTY Ellis

Date Well Completed 9/16/92

Plugging Commenced 9/16/92

Plugging Completed 9/16/92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE#(913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/15/92 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? will send with ACO-1

Producing Formation NA Depth to Top NA Bottom NA T.D. 3675 (R.T.D.)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From surface	To	Size	Put in	Pulled out
			263'	8 5/8"	263'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plug with 190 sx 60/40 pozmix cement w/6% gel and 48# FLO Seal as follows: 25 sx @ 1450', 100 sx @ 770', 40 sx @ 300', 10 sx @ 40', and 15 sx in rathole.

(If additional description is necessary, use BACK of this form.) **RECEIVED** STATE CORPORATION COMMISSION

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 10-22-1992

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc. CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.


Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 92

[Signature]  
Notary Public



Commission Expires: 1-10-95