

15-051-21806-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21806

LEASE NAME Gasaway

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 1 TWP. 11 SRGE. 19 (X) of (W)

COUNTY Ellis

Date Well Completed 1-18-80

Plugging Commenced 8-29-85

Plugging Completed 8-29-85

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.

ADDRESS P.O. Box 470442, Tulsa, Oklahoma 74147

PHONE # 918 492-1694 OPERATORS LICENSE NO. 6273

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Well and Lease were purchased from Leben-Energy Service Corp.

Is ACO-1 filed? NA If not, is well log attached? Yes

Producing Formation Lansing-KC Depth to Top 3201 Bottom 3426 T.D. 3588

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing-KC</u>	<u>Oil</u>	<u>3222</u>	<u>3427</u>	<u>8 5/8"</u>	<u>207"</u>	<u>None</u>
				<u>4 1/2"</u>	<u>3588'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump down 4 1/2" casing: 4 sacks of hulls, then 50 sacks of cement, then 1 sack of hulls, then wiper plug, then 100 sacks of cement, casing filled to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Cementing, Inc. License No. _____

Address Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Robert R. Price, President, Robert R. Price Opera., Inc. (Operator) of above-described well, being first sworn on oath, says: That I have knowledge of the facts, statements, and matters herein and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 470442, Tulsa, Ok. 74147

OCT 23 1985
10-23-1985

CONSERVATION DIVISION

SUBSCRIBED AND SWORN to before me this 21st. day of October, 19 85

Doris Jean Floyd
Notary Public

My Commission Expires: September 5, 1989



WELL LOG

COPY FOR YOUR INFORMATION

15-051-21806-00-00


COMPANY Energy Service Corporation, and Theodore Leben, as an individual
FARM GASAWAY NO. 1

SEC. 1 T. 11S R. 19W
LOC. C NE NE NE

RID. NO. 15
TOTAL DEPTH 3588'

COUNTY Ellis KANSAS

COMM. 10-20-79 COMP. 11-1-79



CONTRACTOR Murfin Drilling Company

CASING

20 10
15 8-5/8" csg. set @ 207' w/145 sx. of Sunset. ELEVATION
12 6
13 5
4 1/2" csg. set @ 3582' w/150 sx. of 60-40 posmix. PRODUCTION
FIGURES INDICATE BOTTOM OF FORMATIONS

130' Surface Dirt-Clay & Shale
207' Shale
213' Cement & Plug & Shale
770' Shale
980' Sand
1045' Shale (Red Bed)
1299' Shale
1334' ANHYDRITE
2370' Shale
3115' Shale & Lime
3180' Lime & Shale
3432' Lime
3588' Lime (Chert) R T D

State of KANSAS
County of SEDGWICK } ss:


I, Wm. S. Shropshire, Asst. Gen. Mgr. of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the GASAWAY #1 well.

Wm. S. Shropshire
Wm. S. Shropshire, Asst. Gen. Mgr.

Subscribed and sworn to before me this 15th day of November 1979

My Commission Expires:



Linda Lynch
Linda Lynch
RECEIVED
STATE CORPORATION COMMISSION

10-23-1985
OCT 23 1985